


TASMANIAN STANDARD DRAWINGS



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA


TAS Division




Local Government Association Tasmania

PARTICIPATING LOCAL COUNCILS

Cradle Coast Region



Northern Region



Southern Region



SHEET INDEX

GENERAL DRAWINGS

- TSD-G01.v1 TRENCH REINSTATEMENT FLEXIBLE PAVEMENTS
- TSD-G02.v1 ROADS TYPICAL PROPERTY ACCESS
- TSD-G03.v1 TRENCH EXCAVATION LIMITS ADJACENT TO FOOTINGS
- TSD-G04.v1 REFERENCE POINTS

STANDARD ROAD DRAWINGS

- TSD-R01.v1 RURAL ROADS UNSEALED
- TSD-R02.v1 RURAL ROADS SEALED
- TSD-R03.v1 TRUCK ACCESS TO RURAL PROPERTIES 'TYPE A'
- TSD-R04.v1 RURAL ROADS TYPICAL PROPERTY ACCESS
- TSD-R05.v1 RURAL ROADS TYPICAL DRIVEWAY PROFILE
- TSD-R06.v1 URBAN ROADS TYPICAL SECTION AND PAVEMENT WIDTHS
- TSD-R07.v1 URBAN ROADS CUL-DE-SAC TURNING HEADS
- TSD-R08.v1 TYPICAL CUL-DE-SAC DETAILS URBAN AND RURAL
- TSD-R09.v1 URBAN ROADS DRIVEWAYS
- TSD-R10.v1 URBAN ROADS DRIVEWAYS WATER SENSITIVE DESIGN
- TSD-R11.v1 URBAN ROADS FOOTPATHS
- TSD-R12.v1 SUB SOIL DRAINS CONSTRUCTION DETAILS
- TSD-R13.v1 SUB SOIL DRAINS PIT CONNECTION TYPE FD
- TSD-R14.v1 CONCRETE KERBS AND CHANNELS DIMENSION
- TSD-R15.v1 CONCRETE KERBS AND CHANNELS CONSTRUCTION DETAILS
- TSD-R16.v1 CONCRETE KERBS AND CHANNELS VEHICULAR CROSSINGS
- TSD-R17.v1 CONCRETE KERBS AND CHANNELS GRATED WEDGE CROSSINGS
- TSD-R18.v1 CONCRETE KERBS AND CHANNELS ACCESS RAMPS
- TSD-R19.v1 BLUESTONE KERBS AND CHANNELS CONSTRUCTION DETAILS
- TSD-R20.v1 TRAFFIC ISLANDS
- TSD-R21.v1 ROAD HUMPS, THRESHOLDS AND ROUNDABOUTS
- TSD-R22.v1 BUS BAYS
- TSD-R23.v1 SIGNS
- TSD-R24.v1 LINE MARKING PARKING CONTROL AND SIGNAGE
- TSD-R25.v1 GUIDE POSTS
- TSD-R26.v1 DELINEATORS
- TSD-R27.v1 CLEAR ZONE, TREATED PINE FENCE
- TSD-R28.v1 W-BEAM INSTALLATION DETAILS
- TSD-R29.v1 W-BEAM TERMINAL TREATMENT
- TSD-R30.v1 W-BEAM APPROACH/DEPARTURE FLARES
- TSD-R31.v1 BARRIERS/GUARDS RAIL RIGID BOLLARDS
- TSD-R32.v1 BARRIERS/GUARDS RAIL LOCKABLE BOLLARDS
- TSD-R33.v1 STONEWALLS/ROCK PITCHING
- TSD-R34.v1 STAIRWAY CONSTRUCTION
- TSD-R35.v1 PEDESTRIAN FENCES
- TSD-R36.v1 TREE/SHRUB PLANTING

STANDARD STORMWATER DRAWINGS

- TSD-SW01.v1 PIPE INSTALLATION ANCHOR BLOCKS
 - TSD-SW02.v1 MANHOLES 100 – 600 DIA. PIPES GENERAL ARRANGEMENTS
 - TSD-SW03.v1 MANHOLES 100 – 600 DIA. PIPES BENCHING DETAILS
 - TSD-SW04.v1 SIDE ENTRY PITS GRATED AND FRAME DETAILS
 - TSD-SW05.v1 SIDE ENTRY PITS (SEP)
 - TSD-SW06.v1 SIDE ENTRY PITS (SEPS)
 - TSD-SW07.v1 SIDE ENTRY PITS TYPE 1
 - TSD-SW08.v1 SIDE ENTRY PITS TYPE 2
 - TSD-SW09.v1 SIDE ENTRY PITS TYPE 3
 - TSD-SW10.v1 SIDE ENTRY PITS TYPE 4
 - TSD-SW11.v1 SIDE ENTRY PITS KERB TRANSITIONS
 - TSD-SW12.v1 SIDE ENTRY PITS TYPE 5
 - TSD-SW13.v1 SIDE ENTRY PITS TABLE DRAIN PIT CONSTRUCTION
 - TSD-SW14.v1 STORMWATER (GVP)
 - TSD-SW15.v1 STORMWATER (GP)
 - TSD-SW16.v1 SIDE ENTRY PITS TYPE 6
 - TSD-SW17.v1 OUTLET HEADWALLS 300 – 600 DIA PIPES
 - TSD-SW18.v1 OUTLET HEADWALLS 1050 – 1350 DIA PIPES
 - TSD-SW19.v1 CONCRETE ENDWALL PLAIN (300 – 450 DIA)
 - TSD-SW20.v1 OUTLET HEADWALLS GROUTED STONE (300 – 450 DIA)
 - TSD-SW21.v1 INLET HEADWALLS GRATED INLET 300 – 900 DIA PIPES
 - TSD-SW22.v1 INLET HEADWALLS RAISED GRATED INLET (SQUARE)
 - TSD-SW23.v1 INLET HEADWALLS RAISED GRATED INLET (DOMED)
 - TSD-SW24.v1 HEADWALLS INLET GRATED AND FENCE REQUIREMENTS
 - TSD-SW25.v1 STORMWATER PROPERTY CONNECTIONS TO MAINS
 - TSD-SW26.v1 SADDLE CONNECTION TO STORMWATER DRAIN
 - TSD-SW27.v1 REPAIRS/NEW CONNECTION TO STORMWATER DRAIN
 - TSD-SW28.v1 GUIDELINES FOR SEDIMENT CONTROL
-
- TSD-RF01.v1 GUIDE TO INTERSECTION AND DOMESTIC ACCESS
 - TSD-RF02.v1 SIGHT DISTANCE REQUIREMENTS
 - TSD-RF03.v1 LINE MARKING TRAFFIC CONTROL
 - TSD-RF04.v1 SIDE ENTRY PITS HYDRAULIC CAPACITY CURVES
 - TSD-RF04.v1 NATURE STRIP DETAILS
-
- TSD-E01.v1 EXCLUSIONS 1
 - TSD-E02.v1 EXCLUSIONS 2
 - TSD-A01.v1 AMENDMENTS

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-INDEX.v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
INDEX SHEET

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE:
30-11-2013

DWG No.

TSD-INDEX-v1



NON TRAFFICABLE

EXISTING ROADS

EXISTING ROADS

NEW ROADS

• CLASS 4 LOCAL ROADS

• PARKING LANES – ALL ROADS
• FOOTPATHS / DRIVEWAYS

TABLE 1 – TRENCH WIDTH

PIPE TYPE	NOM. DIA. (D)	TRENCH WIDTH*
Concrete	≤ 1500	D + 300
	> 1500	Design required
Other pipes	100	300
	150	450
	225 – 300	600
	450	750
	450 – 1500	D + 600
	> 1500	Design required


* Minimum trench widths may be varied above the pipe overlay zone to meet 'Workplace Standards' requirements. (i.e. Trenches greater than 1.5m deep) Excavations over 1.5m may require risk assessment.

NOTES

1. Pavement = 300 min. Granular or match existing which ever is the greater.
2. Pipe overlay depth
 - All other pipes – Min. 150mm
3. Refer to manufacturers recommendations for bedding, haunching and overlay requirements.
4. Compaction of pipe bedding, haunching and overlay – Refer Table 2.
5. Refer to AS/NZS 3725–2007 Table B1 (H2/HS2 Bedding Support Type)

TABLE 2

MATERIAL TYPE	TEST METHOD	TRAFFICABLE	NON-TRAFFICABLE
Non-cohesive (i.e. Granular)	Density Index (I_D) AS 1289.5.6.1	70	60
Cohesive	Dry Density Ratio (R_D) AS 1289.5.4.1 and AS 1289.5.1.1	95	90



FOOTPATH ADJACENT TO KERB

FOOTPATH ADJACENT TO BOUNDARY

MINIMUM DEPTH OF COVER REQUIREMENTS – FOR UNDERGROUND PUBLIC SERVICES

LOCATION			MINIMUM PIPECOVER REQUIRED (mm)				
			Stormwater	* Water Mains/Connections		Services	
	(dia 100mm or greater)	(dia < 100mm)					
PRIVATE PROPERTY	Not subject to vehicular loading	Backyards, Gardens areas	450	–	–	For electricity, communications and other services, contact the relevant authority for advice.	
	Subject to vehicular loading	Driveways, Parking areas	600	–	–		
PUBLIC PROPERTY	Not subject to vehicular loading	Footpaths, Nature strip	600	600	450		
	Subject to vehicular loading	Vehicular crossing over footpath	600	600	450		
		Non-arterial roads	900	750	600		
		Arterial roads	1200	900	750		
		Gas	–	–	–		750
		Electricity	–	–	–		750
		Communications	–	–	–	600	

* Refer to local water authority for additional cover requirements.

NOTES

1. Conduits may be required for future services, refer to relevant authorities.
2. For electricity, telephone and other services, contact the relevant authorities.
3. May need to increase to accommodate services eg. underground power.
4. All cover is subject to pipe class.
5. Refer to AS/NZS 3725–2007.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-G02-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
URBAN ROADS TYPICAL SERVICE LOCATIONS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE:
30-11-2013

DWG No.

TSD-G02.v1



**PIPELINE – TYPICAL SECTION
(BUILDING ADJACENT TO PIPELINE)
(Shoring not shown for clarity)
N.T.S.**

OBJECTIVES

- Minimise the risk of:
1. damage caused by an adjacent trench excavation to an existing structure due to;
 - a reduction in support of the footing(s)
 - a change in the moisture content in the vicinity of the footing(s).
 2. failure of a pipeline resulting from forces from an adjacent footing in addition to the anticipated backfill and 'In Service' loads on the pipeline.
 3. trench collapse and injury to workers during a pipeline installation as a result of forces applied to the trench sides from an adjacent footing.

APPLICATION

This Standard Drawing applies to Public Utility Pipelines (P.U.P'S including supply mains, drains and conduits).

References:

- AS NZS 3500.2 : 2003 'Plumbing and Drainage' for other pipelines as applicable.
- BCA Housing Provisions
- L.G.A.T. Standard Drawing TSD-G01

NOTES

1. All foundation designs and proposed P.U.P's. must be submitted for approval prior to the commencement of works.
2. The design of footings and pipelines in the vicinity of footings, must be prepared by a suitably qualified and competent person and consider (but not restricted to) the following:
 - footing type and associated loading
 - existing soil types and properties
 - method of construction (footing/pipeline)
 - pipe class, trench support, trench backfill and 'In Service' loading to meet the objectives listed.
3. Table 1, adopted from the B.C.A. Housing Provisions, provides an indication of the range of the 'Zone of Influence' angle associated with different soil types for Cut/Fill situations.

TABLE 1

SOIL TYPE	ANGLE OF SLOPE (H : L)	
	Compacted Fill	Cut
Stable rock*	2: 3	8: 1
Sand*	1: 2	1: 2
Silt**	1: 4	1: 4
Firm clay	1: 2	1: 1
Soft clay	Not suitable	2: 3
Soft soils**	Not suitable	Not suitable

* Most sand and rock sites with little or no ground movement from moisture changes.

** Sites include soft soils, such as soft clay or loose sands, landslip, mine subsidence, collapsing soils, soils subject to erosion, reactive sites subject to abnormal moisture conditions or sites which cannot be classified otherwise.

*** Note: excavations over 1.5m may require benching and or shoring – refer to risk assessment.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-G03-v1.dwg

REFERENCES

© 2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au


TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

LGAT
Local Government Association Tasmania


STANDARD DRAWING
GUIDE TO TRENCH EXCAVATION LIMITS
ADJACENT TO FOOTINGS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013 DWG No. TSD-G03.v1




TYPE KC
(TYPE KCS SIMILAR)




TYPE KCM




TYPE BK




TYPE FK




MANHOLE
(INTERSECTION OF PIPELINES)




TYPE PCM




ACCESS RAMP




ROUNDBABOUT
(CENTRE OF RADII)




TRAFFIC ISLANDS
(CENTRE OF RADII)




HEADWALL



VEHICULAR CROSSING



RETAINING WALL



SIDE ENTRY PIT – AS SHOWN
(OTHER PITS – PIT CENTRE UNLESS NOTED)

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-G04-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING

REFERENCE POINTS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-G04.v1



TYPICAL CROSS SECTION

SCALE 1 : 50

TABLE 1

SOIL / ROCK TYPE	EMBANKMENT		CUTTING	
	Vertical	Horizontal	Vertical	Horizontal
Solid Rock	—	—	1.00	0.25
Loose Rock	1.00	2.00	1.00	1.33
Sand	1.00	3.00	1.00	3.00
Stiff Clay	1.00	1.00	1.00	1.00
Soft Clay	1.00	3.00	1.00	1.50

TABLE 2

CODE*	A.A.D.T.	(w) TRAFFIC WIDTH	GRAVEL SHOULDER	VERGE	PAVEMENT WIDTH	LOGGING ROUTE	HEAVY VEHICLES	BUS ROUTE	Bends with < 60m sight line
US1	<30	4000 (S)	500	NO	5	NO	< 5%	NO	w + 1000
US2	30 - 100	4000 (S)	1000	NO	6	YES < 5%	< 5%	YES	w + 1000
US3	100 - 300	5500 (D)	1000	NO	7.5	YES	< 10%	YES	w + 500
US4	> 300	6000 (D)	1000	NO	8	YES	> 10%	YES	w + 500

*To satisfy a Road Class (eg. US3) the capability to comply with A.A.D.T, LOGGING ROUTE, HEAVY VEHICLE and BUS ROUTE is necessary.


(S) - SINGLE LANE
(D) - DUAL LANE

NOTES

- Alignment to satisfy min. Design speed.
- Roadside table drains, cut off drains and culverts to be installed to suit topography.
- Provision for widening or passing bays may be required where sight distance requirements cannot be met or there are limited options for vehicles to pull off the road.
- Refer Sheets TSD-R25, TSD-R28, TSD-R29 and TSD-R30 for Guide Post / Guard Rail installation.
- Refer to Austroads AGRD-10 Part 6: Roadside Design, Safety and Barriers
- Design of pavements to consider project traffic loading, sub-grade strength and comply with the procedures in either:
 - A.R.R.B. A.P.R.G. Report no. 21, A Guide to the Design of New Pavements for Light Traffic.
 - Austroads - Pavement Design (2004) 'A Guide To The Structural Design Of Road Pavements'



<p>SCALES: AS SHOWN (All scales are correct at A3)</p> <p>XRef File: TSD-R01-v1.dwg</p>	<p>REFERENCES</p>	<p>©2012 This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited. It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au</p>	<p>TAS Division IPWEA INSTITUTE OF PUBLIC WORKS ENGINEERING AUSTRALIA</p>	<p>LGAT Local Government Association Tasmania</p>	<p style="text-align: center;">STANDARD DRAWING RURAL ROADS UNSEALED</p> <p style="font-size: small;">GPO Box 1521, Hobart Tasmania 7001 326 Macquarie Street, Hobart Tasmania 7000 T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au</p> <p style="font-size: x-small;">ISSUE DATE: 30-11-2013 DWG No. TSD-R01-v1</p>
---	-------------------	--	--	--	--



TYPICAL CROSS SECTION

SCALE 1 : 50



NOTES

1. Alignment to satisfy min. Design speed.
2. Roadside table drains, cut off drains and culverts to be installed to suit topography.
3. Provision for widening or passing bays may be required where sight distance requirements cannot be met or there are limited options for vehicles to pull off the road.
4. Refer Sheets TSD-R25, TSD-R28, TSD-R29 and TSD-R30 for Guide Post/ Guard Rail installation.
5. Refer to Austroads AGRD-10: Part 6 Roadside Design, Safety and Barriers.
6. Design of pavements to consider project traffic loading, sub-grade strength and comply with the procedures in either:
 - A.R.R.B. A.P.R.G. Report no. 21, A Guide to the Design of New Pavements for Light Traffic.
 - Austroads - Pavement Design (2011) 'A Guide To The Structural Design Of Road Pavements'
7. 0.4 metres required if edge line is to be installed.
8. Two coat 'Hot Bitumen' spray seal. Aggregate 10/7 or 14/7 optional.
9. Surface type to be determined with consideration to, Vehicle types/turning movement, location and grade.

TABLE 1

SOIL / ROCK TYPE	EMBANKMENT		CUTTING	
	Vertical	Horizontal	Vertical	Horizontal
Solid Rock	-	-	1.00	0.25
Loose Rock	1.00	2.00	1.00	1.33
Sand	1.00	3.00	1.00	3.00
Stiff Clay	1.00	1.00	1.00	1.00
Soft Clay	1.00	3.00	1.00	1.50

TABLE 2

CODE*	A.A.D.T.	EXISTING INFRASTRUCTURE	NEW DEVELOPMENT	SEALED SHOULDER	GRAVEL SHOULDER	VERGE	PAVEMENT WIDTH	LOGGING ROUTE	HEAVY VEHICLES	BUS ROUTE	Bends with < 60m sight line
		(w) SEALED TRAFFIC WIDTH	(w) SEALED TRAFFIC WIDTH								
S1	< 30	4000 (S)	-	-	500	NO	5000	NO	< 5%	NO	w + 1000
S2	30 - 100	4000 (S)	-	-	1000	NO	6000	YES < 5%	< 5%	YES	w + 1000
S3	100 - 300	5500 (D)	5500 (D)	400 ^{Refer Note 7.}	500	500	6500	YES	< 10%	YES	w + 500
S4	300 - 2000	6000 (D)	6000 (D)	400 ^{Refer Note 7.}	500	500	7000	YES	> 10%	YES	w + 500
S5	> 2000	7000 (D)	7000 (D)	500	500	500	9000	YES	> 10%	YES	w + 500

*To satisfy a Road Class (eg. S3) the capability to comply with all A.A.D.T, LOGGING ROUTE, HEAVY VEHICLE and BUS ROUTE is necessary.

(S) - SINGLE LANE
(D) - DUAL LANE

SCALES: AS SHOWN
(All scales are correct at A3)

REFERENCES

XRef File: TSD-R02-v1.dwg

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




STANDARD DRAWING
RURAL ROADS
SEALED

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-R02-v1



TYPE HW
SCALE 1: 10

Form Table Drains as required, direct flows to Road table drain

KEY


- HW - Head Wall
- DCE - Driveable Culvert Endwall



TABLE 1

Vehicle Standing (V.S)	* 'L' m
Car	6.0
Truck / Car + Trailer	V.S Length + 1.0


* Increase 'L' as required to suit outward swinging gates.




TYPE DCE
SCALE 1: 10

NOTES

1. Property Access Seal Types:
 - Adopt the seal type on the adjacent road (Asphalt / hot Sprayed bituminous surfacing).
 - Seal is not required for property access off unsealed roads.
2. Offset property entrance gate to provide adequate vehicle standing area clear of road edge, as required.
3. Install guideposts at :
 - culvert end walls.
 - the start of the access ('nearside' lane approach only).
4. Pipe Culvert.
 - Pipe size, type, class, cover and grade shall be determined by consideration of the drainage catchment, rainfall I.F.D. data and road grade for an A.R.I. of 5 years (min).
 - Minimum pipe size - 300 dia.
 - Minimum grade - 1 in 100 (1%).
5. Shallow dish crossing may be used as an alternative.
6. Applicable for design speed zones in excess of 60km/hr.



CROSS SECTION



DRIVEWAY PROFILE

Culvert removed for clarity

NOTES

- All dimensions in millimetres (mm) unless noted
- Precast endwall to be winged type or other approved type.
- Shallow dish crossing may be used as an alternative
- Min clear cover over driveway culverts shall be:

Pipe Class:	Min Cover:
-Class 2 (Concrete)	600
-Class 3 (Concrete)	400
-Class 4 (Concrete)	300

 (All other pipes refer to manufacturers recommendations.)
- Install guideposts at culvert ends.
- Minimum driveway dimension for Class 4b to have a minimum pavement width of 4 metres.


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R04-v1 .dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
RURAL ROADS
TYPICAL DRIVEWAY PROFILE

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No.

TSD-R04-v1



KEY
 HW - Head Wall
 DCE - Driveable Culvert Endwall

DRIVEWAY TYPE 'A' CATERS FOR:	LENGTH
Long Rigid Trucks	12.5m
Long Mini B-Doubles	19.0m
Truck + Trailer Combinations	19.0m

STANDARD OBJECTIVES

1. Maximise road safety.
2. Reduce the extent of debris being tracked onto the roadway.
3. Provide vehicle standing area clear of the road edge.
4. Contain stormwater runoff within the road table drains.

NOTES

1. Property Access Seal Types:
 - Adopt the seal type on the adjacent road (Asphalt / Hot Sprayed bituminous surfacing).
 - Seal is not required for property access off unsealed roads.
2. Offset property entrance gate to provide adequate vehicle standing area clear of road edge, as required.
3. Install guideposts at :
 - culvert end walls.
 - the start of the access ('nearside' lane approach only).
4. Pipe Culvert.
 - Pipe size, type, class, cover and grade shall be determined by consideration of the drainage catchment, rainfall I.F.D. data and road grade for an A.R.I. of 5 years (min).
 - Minimum pipe size - 300 dia.
 - Minimum grade - 1 in 100 (1%).
5. References.
 - DIER drawing No.3402-2/P35-2.
6. Applicable for design speed zones in excess of 60km/hr.




TABLE 1 – ROAD REQUIREMENTS (RESIDENTIAL)

ROAD TYPES	ROAD TYPE	ROAD LENGTH / NUMBER OF TENEMENTS	MINIMUM ROAD WIDTH	MINIMUM RESERVATION WIDTH	MINIMUM FOOTPATH REQUIREMENTS	NOTES (TABLE 1) a. Road and reservation widths shown are the minimum required. Increased widths for any road class may required to accomodate any or all of the following: • high numbers of commercial vehicles e.g. Buses, Semi Trailers and B-Doubles • high traffic volumes • provision for bicycles b. Intermediate road widths between the following ranges are not permitted. • 6.9m and 8.9m (F.O.K) • 8.9m and 11.0m c. The General Manager's delegated officer. may approve variations to any of the requirements in this Table to suit specific project outcomes. d. Council bylaws apply.
1 – Arterial	Detail design required					
2 – Sub Arterial	Detail design required					
3 – Collector	Through Road	Any length	11.0m	20.0m	Both Sides	
4 – Local	Through Road	Any length	8.9m	18.0m	One Side Only	
	Cul-De-Sac	Length > 150m	8.9m	18.0m	One Side Only	
	Cul-De-Sac	Length ≤ 150m and / or No. of equiv. tenements ≤ 15	6.9m	15.0m	One Side Only	

TABLE 2 – ROAD REQUIREMENTS (COMMERCIAL / INDUSTRIAL)

ROAD CLASS	ROAD TYPE	ROAD LENGTH / NUMBER OF TENEMENTS	MINIMUM ROAD WIDTH	MINIMUM RESERVATION WIDTH	MINIMUM FOOTPATH REQUIREMENTS	NOTES (TABLE 2) 1. Footpath provision to suit Commercial / Industrial development. 2. Notes a. and c. from Table 1.
3 – Collector	Through Road	Detail design required				
4 – Local	Through Road or Cul-De-Sac	Lot Size < 10,000m ²	11.0m	18.0m	(Refer note)	
		Lot Size ≥ 10,000m ²	10.0m	18.0m	(Refer note)	







TABLE 3 – MAXIMUM BATTER SLOPES

MATERIAL TYPE	EMBANKMENT		CUTTING	
	VERT.	HORIZ.	VERT.	HORIZ.
Solid Rock	1	0.25	1	0.25
Loose Rock	1	1.33	1	1.33
Soil	1	1.50	1	1.50
Sand	1	3.00	1	3.00

- NOTES
- G1. Pavement depths shown are the minimum required. Final depths are determined by structural calculations based on the actual sub-grade C.B.R. and design traffic loads, in accordance with the Austroads publication: 'A Guide To The Structural Design Of Road Pavements' The base course is shown to facilitate ease of construction. It may be reduced to a minimum of 100mm, provided the overall pavement depth (including seal) is ≥ 300mm
- G2. References:
 • TSD-R09 & TSD-R10 – Driveways
 • TSD-R11 – Footpaths
- G3. References: Road crossfall greater than 5% must be approved by the General Manager's delegated officer.
- G4. Surfacing type to consider grades/vehicle type and turning movements.




CIRCULAR




OFFSET CIRCULAR (RIGHT HAND SHOWN)

NOTES


- The general layout and dimensions accommodate the wheelpaths for a:
 - Single Movement Turn by a design car – turning circle 12.0m
 - Three Point Turn by a design service vehicle – 8.8m long
- The road pavement shown represents the:
 - extent of pavement construction (No barrier kerbs).
 - face of kerb (barrier kerb type).
 - The minimum 2.0m clearance from the extent of the turning head to the road reserve boundary provides for service conduits, signage, vehicle overhang, pedestrian movement etc.
- Refer Sheet TSD-R06 for:
 - Road width (W) face of kerb to face of kerb.
 - Road reserve width (R)



'TEE'
Option subject to council approval.



'WYE'
Option subject to council approval.



OFFSET SQUARE (LEFT HAND SHOWN)
Option subject to council approval.

KEY

--- ROAD RESERVE

[Stippled Area] NO PARKING ZONE

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R07-v1.dwg

REFERENCES

©2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au

TAS Division

IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA


LGAT
Local Government Association Tasmania

STANDARD DRAWING
URBAN ROADS
CUL-DE-SAC TURNING HEADS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-R07-v1



URBAN TYPE CUL-DE-SAC



RURAL TYPE CUL-DE-SAC

NOTES

1. All dimension in metres (m)
2. Cul-de-sac heads are to be asphalted
3. Minimum 12.5m radius for industrial.
4. For cross fall greater than 5% seek local council approval

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R08-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
TYPICAL CUL-DE-SAC DETAILS URBAN AND RURAL


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R08-v1




TYPICAL PLAN (DOMESTIC)
(‘TYPE KC’ KERB SHOWN)




TYPICAL DRIVEWAY PROFILE
SUITS ‘B85’ / ‘B99’ VEHICLES
(‘TYPE KC’ KERB / FOOTPATH AT KERB SHOWN)



CONCRETE



SEGMENTAL PAVERS



ASPHALT

PAVEMENT DETAILS

(For Sub-grade C.B.R. ≥ 4.0%)

CONSTRUCTION NOTES

1. Concrete surfaces – Edge tooled, broom finish.
2. The Principal may increase depth of base course(s) for subgrade strength (C.B.R. < 4.0%)
3. Extend 10mm compressible joint filler through concrete footpaths only (Refer sheet TSD-R11, Footpaths).

DESIGN NOTES


4. Design driveway profiles (tabulated) are in accordance with the requirements of ‘AS/NZS 2890.1 : 2004’ using ‘Standard Design Vehicles’:
 - B85 Vehicle – Domestic driveways (including 1 – 2 units)
 - B99 Vehicle – Light commercial, large unit development.
5. An approved engineering design is required for varying site conditions and for driveways used by ‘Non Standard’ vehicles, detailing the structural, plan geometry and vertical profile requirements.

DIMENSION TABLE – PLAN VIEW		
Dim.	Description	Notes
A	Boundary Offset	New Subdivisions – 1000mm min. Established areas – Match existing
B	Transition (Wing)	Types ‘KC’ and ‘KCM’: B = 1000mm
C	Min. kerb Length	Delete transitions and construct continuous crossing if ‘C’ IS < 500mm

SCALES: AS SHOWN
(All scales are correct at A3)

REFERENCES

©2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au




STANDARD DRAWING
URBAN ROADS
DRIVEWAYS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No. TSD-R09-v1


XRef File: TSD-R09-v1.dwg




PERSPECTIVE VIEW



TYPICAL SECTION (DOMESTIC)



PLAN



DETAIL A

CONSTRUCTION NOTES

1. Concrete surfaces – Edge tooled, broom finish.
2. The Principal may increase depth of base course(s) for subgrade strength (C.B.R. < 4.0%)
3. Extend 10mm compressible joint filler through concrete footpaths only (Refer sheet TSD-R11, Footpaths).
4. The thickness of decorative surfacing, where approved, is additional to thickness shown.
5. An approved engineering design is required for varying site conditions and for driveways used by 'Non Standard' vehicles, detailing the structural, plan geometry and vertical profile requirements.
6. This crossing is not for commercial vehicles.
7. All concrete to be grade N25 (min)
8. Distance from nominal face of kerb may vary with swale width. Grades are recommended maximums for vehicle access.
9. Dimensions in millimetres (U.N.O)

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-R10-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
URBAN ROADS DRIVEWAYS
WATER SENSITIVE DESIGN




GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R10-v1



PAVED
ASPHALT
CEMENT STABILISED STONE DUST
PAVEMENT DETAILS
SCALE 1 : 10



ADJACENT TO KERB
SCALE 1 : 10



PLAN
SCALE 1 : 50
REINFORCED CONCRETE FOOTPATH



NOTES

- Concrete – N25, nominal 60 slump continuously broom finish surface.
- Generally 'W' = 1.5m when footpath is adjacent to kerb and channel and elsewhere. The General Manager's delegated officer may:
 - Approve reduced footpath width where pedestrian traffic is low or where physical constraints exist. Min width 1.2m.
 - Require increased footpath width where pedestrian traffic is high.
 - Require increased footpath width to 1.8m around head of culs-de-sac adjacent to kerb and channel.
- The General Manager's delegated officer may:
 - Approve crossfalls to a maximum of 4% where physical constraints exist.
 - Increase depth of base course(s) for sub-grade strength (C.B.R. < 4.0%)
- Treated pine to comply with 'AS.1604-1997' (Timber – Preservative Treated – Sawn and Round).
- Fibre reinforcement are permissible but must be approved by general manager's delegated officer of local council.

TABLE 1

PAVER TYPE	BASE 'CLASS A'
65mm Clay	75mm
40mm Concrete	100mm
60mm Concrete	80mm

TABLE 2 – SAND GRADINGS FOR PAVERS

AS. SIEVE SIZE (mm)	BEDDING SAND		JOINTING SAND	
	CONCRETE	CLAY	CONCRETE	CLAY
	% PASSING		% PASSING	
9.52	100	100		
4.75	95 – 100	90 – 100		
2.36	80 – 100	75 – 100	100	100
1.18	50 – 85	55 – 90	90 – 100	75 – 95
600 Microns	25 – 60	35 – 59	60 – 90	50 – 80
300 Microns	10 – 30	8 – 30	30 – 60	20 – 45
150 Microns	5 – 15	0 – 10	15 – 30	5 – 15
75 Microns	0 – 10	0 – 5	5 – 10	0 – 5


* Refer 'Approved Products List' for jointing sand stabilisers and paving sealants.

SUBGRADE CLASSIFICATION


EXPANSIVE NATURE	LIQUID LIMIT (%)	PLASTICITY INDEX	P.I. x % < 0.425mm	POTENTIAL SWELL (%)
Very high	> 70	> 45	> 3200	> 5.0
High	> 70	> 45	2200 - 3200	2.5 - 5.0
Moderate	50 - 70	25 - 45	1200 - 2200	0.5 - 2.5
Low	< 50	< 25	< 1200	< 0.5

NOTES


1. Sub-base more permeable than base.
2. Refer 'Vic Roads' Technical Bulletin 37 (September 1993) for additional information.




LOW EXPANSIVE CLAY SUBGRADES
'TYPE CR' SHOWN



MEDIUM TO HIGH EXPANSIVE CLAY SUBGRADES
'TYPE CR' SHOWN



**PIPE SLOTS
DETAIL**



NOTE

1. 'Type CR' and 'Type FD' may be used for either situation.

FILTER MATERIAL

TYPE CR
Coarse gravel or crushed rock (no fines or organic matter) Partial size: • Maximum - 19mm • < 5% by mass passing 4.75mm sieve

TYPE FD	
AS. Sieve Size	% Material passing
4.75 mm	95 - 100
2.36 mm	65 - 95
600 um	15 - 65
300 um	5 - 15
150 um	0 - 5
75 um	0 - 5

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R12-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




STANDARD DRAWING
SUB SOIL DRAINS
CONSTRUCTION DETAILS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R12-v1




SIDE OUTLET




SIDE OUTLET




SECTION A-A



SECTION B-B



END OUTLET



END OUTLET

FIN DRAIN CONNECTION DETAILS
(AT SIDE ENTRY PITS)

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-R13-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
SUB SOIL DRAINS
PIT CONNECTION - TYPE FD


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R13-v1




TYPE KC
(KERB AND CHANNEL)
SCALE 1 : 20




TYPE KCS
(SMALL)
SCALE 1 : 20




TYPE KCM
(MOUNTABLE)
SCALE 1 : 20




TYPE KCM2
(MOUNTABLE)
SCALE 1 : 20




TYPE BK
(BARRIER)
SCALE 1 : 10




TYPE KC
VEHICULAR CROSSING
SCALE 1 : 20
* Refer note 2.




TYPE KCS
VEHICULAR CROSSING
SCALE 1 : 20




TYPE KCM
VEHICULAR CROSSING
SCALE 1 : 20




VEE CHANNEL
VEHICULAR CROSSING
SCALE 1 : 20




TYPE DD
(DISH DRAIN)
SCALE 1 : 10




OPEN WEDGE
VEHICULAR CROSSING
SCALE 1 : 20



TYPE FK
(FLUSH)
SCALE 1 : 10



TYPE PCM
(PRECAST MOUNTABLE or Poured ON SITE)
SCALE 1 : 10




ASPHALT WEDGE
VEHICULAR CROSSING
SCALE 1 : 20

(Approval needed by General manager's delegated officer)

NOTES

- Radius (25mm) all exposed edges unless otherwise noted.
- The height of the 'Type KC' crossover may be reduced from 250mm, by up to 50mm to improve vehicle clearance, subject to the road drainage requirements being satisfied by either:
 - confirming, by calculation, the flow contained within the road reserve OR
 - Provision of additional drainage.
- All concrete kerb and channel shall be constructed in accordance with AS2878-2000
- Provide tooled contraction joints at 3m max centres.
- Jointing Requirements - Typical for all, provide expansion joints at 21m centres and at structures such as access ramps, vehicular crossings, gully pits and tangent points at intersection kerb returns.



GRATED WEDGE
VEHICULAR CROSSING
SCALE 1 : 20

Refer Sheet TSD-R17 for grate details



SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R14-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited. It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
APPROVED CONCRETE KERBS AND CHANNELS
PROFILE DIMENSIONS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R14-v1



ASPHALT FOOTPATH / NATURE STRIP
(TYPES BK, KC AND KCS)
SCALE 1 : 25




PAVED FOOTPATH
(TYPES KC AND KCS)
SCALE 1 : 25




TYPE KCM
SCALE 1 : 25

* Refer to TSD-R11 for paving details.


STORMWATER KERB OUTLETS




TYPE KC / KCM
(CONSTRUCTION IN EXIST. PAVEMENT)
SCALE 1 : 20




TYPE KCS
(CONSTRUCTION IN EXIST. PAVEMENT)
SCALE 1 : 20



TYPE BK
(CONSTRUCTION IN NEW PAVEMENT)
SCALE 1 : 20



TYPE FK
(e.g. EDGE RESTRAINT FOR PAVING)
SCALE 1 : 20



TYPE DD
(GRASSED AREA)
SCALE 1 : 20

NOTES

- Sub-Base Depth
 - Sub-grade C.B.R. \geq 4% - Depth = Min. 135mm.
 - Sub-grade C.B.R. < 4% - 'Class B' geotextile, Min. 150
- Pavement Design


Design of pavements to consider project traffic loading, sub-grade strength and comply with the procedures in either:

 - A.R.R.B. special report No. 41 - 'A Structural Design Guide For Flexible Residential Street Pavements'.
 - AUSTROADS 'A Guide To Pavement Technology Part 2: Pavement Structural Design'

- Jointing Requirements (Typical for all)

Provide contraction joints at 3.0m centres.
Provide expansion joints at the following:

 - 21.0m centres (Max.)
 - Structures such as access ramps, vehicular crossings, gully pits and tangent points at intersection kerb returns.



SCALE - 1 : 20


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R15-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
CONCRETE KERBS AND CHANNELS
CONSTRUCTION DETAILS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R15-v1




TYPE KC
UNREINFORCED
SCALE 1 : 20




TYPE KCS
UNREINFORCED
SCALE 1 : 20



TYPE KCR & B1 (HEAVY VEHICLES)
IN-SITU POURED REINFORCED
SCALE 1 : 20
(Types KCS and KCM similar)



TYPE KCM
UNREINFORCED
SCALE 1 : 20



TYPE KCRB & B1 (HEAVY VEHICLES)
EXTRUDED ON REINFORCED BASE
SCALE 1 : 20
(Types KCS and KCM similar)

NOTES

1. Sub-Base Depth
 - Sub-grade C.B.R. \geq 4% - Depth = Min. 135mm.
 - Sub-grade C.B.R. < 4% - Include 'Class B' geotextile.
2. Refer Sheet TSD-R14 for additional dimensions.
3. All works to be inspected prior to pouring concrete
4. Any concrete oxide to be worked into the concrete surface during finishing.
5. All dimensions in millimetres (mm)



SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-R16-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
CONCRETE KERBS AND CHANNELS
VEHICULAR CROSSINGS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R16-v1




TYPICAL SECTION
SCALE 1 : 10
(Council Specific Approval only)



FRONT VIEW



PLAN VIEW
** 485mm for half metre end sections
GRATE AND FRAME DETAIL
SCALE 1 : 10
(Council Specific Approval only)



END TRANSITION DETAIL
N.T.S.

NOTES

TRANSITION BARS

- Objective
To minimise the risk of personal injury and vehicle damage for all road users (in particular 2 wheeled vehicles) resulting from impact with the exposed end of the wedge grate.
- Install Transition Bars on traffic 'approach side' only, as specified. Typically installed where the:
 - through lane is adjacent to kerb
 - bicycle traffic is significant
 - speed environment is higher
- Transition Bars – Supplied by Principal.
- Grate and Frame
 - All welds – Nominal 5mm continuous fillet / butt.
 - Clean up weld spatter and remove sharp edges prior to hot dip galvanising



SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R17-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




STANDARD DRAWING
CONCRETE KERBS AND CHANNELS
GRATED WEDGE CROSSINGS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R17-v1



ACCESS RAMP – TYPE A



STANDARD PROFILE – SP



ALTERNATIVE PROFILE – AP

SECTION A – A

TABLE 1

RAMP LENGTH	L (mm)	
	900 to 1520	1520 to 2000
Maximum Grade	1 in 8 (12.5%)	1 in 14 (7.14%)
Minimum Grade	1 in 8.5 (11.5%)	* Refer note 2.
Wing (W)	600 Min. 1200 Max.	Refer FIG. 1 Refer FIG. 2







FIG. 1



ACCESS RAMP – TYPE B



SECTION B – B



TYPICAL DETAIL – ADJACENT RAMPS




FIG. 2

NOTES

- Use 'Type A' ramp where 1330 clearance can be provided, otherwise use 'Type B'.
- Provide TGS.I.'s (Individual Tactile Surface Indicators) where ramp slope is less than 12.5% as directed by the Superintendent. (Refer 'AS/NZS 1428.4 – 2002')
- Place SL72 mesh centrally in all ramps including adjacent channel.
- Concrete strength – N25, provide 25mm radius on exposed edges.
- Return 'Type B' kerb at 90° to back of kerb when the footpath comes to an end (one ramp only). Use 0.3m radius to face of kerb in bends.
- Finish – all exposed surfaces
 - Provide tooled joint transition at junction of ramp and wings.
 - Heavy surface dusting of a 1 : 1 mix of cement and sharp quartz sand.
 - Trowelled in and finished with a broomed, non slip finish.
- Design drawings or ID Assets Department will nominate Raised or Flush.

References

 - AS/NZS 1428.4 – 2002
 - Refer to Local Council – Pedestrian Tactile Indicators


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R18-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
CONCRETE KERBS AND CHANNELS
ACCESS RAMPS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R18-v1




CROSS SECTION
TYPES BS AND BSR
 N.T.S.




CROSS SECTION
TYPE BSR - CROSSING
 N.T.S.




TYPE BSK
BLUESTONE BARRIER KERB
 N.T.S.



TYPE BS
KERB AND CHANNEL
 TYPICAL PLAN



TYPE BSR
KERB AND CHANNEL
 TYPICAL PLAN



TYPE BSR
VEHICULAR CROSSING
 TYPICAL PLAN

NOTES

1. Mortar:
 - 1.5 parts putty sand
 - 1.0 part quartz sand
 - 1.0 part cement
 - Nominal joint width 20 - 50mm
 - Finish flush with stone faces.
2. Re-use suitable existing bluestone.
3. Construct concrete access ramps as required.

SCALES: AS SHOWN
 (All scales are correct at A3)

XRef File: TSD-R19-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
 It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
 ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING
BLUESTONE KERBS AND CHANNELS
CONSTRUCTION DETAILS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
 T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-R19-v1





TABLE 1 – 'PCM' Units

RADIUS	BLOCK LENGTH
<8m	300
8m – 14m	750
14m – 25m	1200
>25m	1800

Bed kerb units on hot asphalt or cement grout (3 parts sharp quartz sand to 1 part cement)





**TYPE PCM
FIXING DETAILS**
N.T.S.


Refer Sheet TSD-R14 for kerb dimensions

NOTES


- Concrete 'Bullnose' (Insitu poured)
 - N32 Conc. Shaped to suit kerb
 - Cast over 150 x 10mm decking spikes or 150 grouted R12 reo. bar (Min 2 off, 80mm embedment)
 - End radius – 300mm unless noted.
- Reinforced Concrete Infill
 - 120mm thick, SL72 mesh central
 - N25 – non trafficable.
 - N32 – trafficable.
 - Sandstone coloured stamped 210mm x 180mm stretcher bond pattern – unless specified on project drawings.
- Asphalt / C.S.S.D. Infill
 - Nom. 85mm cement stabilised stone dust (2.0%).
 - 35mm Asphalt (AC7)
 - Asphalt pavement pattern / colouring – as specified.
- Paved Infill
 - Paver type and colour nominated on project drawings.
 - Provide subsoil drain for paved infill.
- The 200 (1 in 20) taper is only required for a 'stand alone' traffic island. Omit 'Hazard board' and install 'Keep left' signs for non Pedestrian refuge island.
- The example shown is for the first island in a series. Intermediate islands do not require the 200 (1 in 20) taper.
- Refer D.I.E.R. drawing G/10/405 for Pedestrian Refuge for detail not shown.




Height and placement maybe dependant on vertical alignment of road.
Approval of specific instances by D.I.E.R. and the Director Infrastructure Services..




FLAT TOP HUMP
SECTION A - A
SCALE 1 : 25



DETAIL A
EDGE RESTRAINT - PAVERS ONLY
SCALE 1 : 10




WATTS PROFILE HUMP
SECTION A - A
SCALE 1 : 25





TYPICAL THRESHOLD TREATMENT
N.T.S.

TABLE 1

L (m)	H (mm)
0.0	100
0.1	100
0.2	99
0.3	97
0.4	95
0.5	93
0.6	90
0.7	86
0.8	81
0.9	76
1.0	71
1.1	65
1.2	58
1.3	51
1.4	43
1.5	34
1.6	25
1.7	16
1.8	5




WATTS PROFILE HUMP
PLAN - LINE MARKING
SCALE 1 : 100




TYPICAL SECTION THROUGH ROUNDABOUT
N.T.S.

NOTES

1. Refer 'AS.1742.13-2009' for line marking details.
2. Department of Infrastructure Energy and Resources approval is required for all traffic management installations.




TYPE 1
PARALLEL INDENTED
SCALE 1 : 250




TYPE 2
ANGLE INDENTED
SCALE 1 : 250


** Radii as per 'Type 1'




TYPE 3
EXISTING KERB
SCALE 1 : 250



TYPE 4
EXISTING KERB
SCALE 1 : 250



UNSIGNALED
INTERSECTION
N.T.S.



SIGNALED
INTERSECTION
N.T.S.

NOTES

1. Refer Sheet TSD-R24 for bus bay signage requirements.
2. Dimensions of bays are designed to allow a 12.5 metre 'Metro' Accessible bus to stop parallel with the kerb.



SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R22-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING

GUIDE TO BUS BAYS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R22-v1




TRAFFIC / PARKING SIGNS
SCALE 1 : 20



PLAN VIEW
KERBSIDE PARKING SIGNS
SCALE 1 : 20



POST KEY
SCALE 1 : 5



TRAFFIC ISLANDS
SCALE 1 : 20

Height and placement maybe dependant on vertical alignment of road.
Approval of specific instances by D.I.E.R. and the General Manager's
delegated officer.



NOTES

1. Place key on the kerbside face of the post clear of pedestrian traffic.
2. Install post sleeves flush with the footpath / nature strip.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-R23-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING
SIGNS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No.

TSD-R23-v1

CODE

PURPOSE

LINE MARKINGS / SIGNAGE

LINE WIDTH (mm)

RESPONSIBILITY

NS


NO STOPPING (All vehicles)
Yellow paint



100

PM


METERED PARKING BAYS
White paint



100

PT

'TIME LIMITED' PARKING BAYS
(Non metered - e.g. 2 Hour)
White paint




100

Local Council


PA

ANGLED PARKING BAYS
White paint




100

SPECIFIC USE ZONES
(e.g. Loading, Taxi, Truck)
Signs only



BUS ZONES
Signs only



Zone signs - Local Council
Bus Stop sign - Metro

NOTES

1. Define bays in 'Time Limited' parking bays ONLY where specified.
2. Provide nominal 100mm gap between line and edge of seal.
3. Provide signs with closed arrows each end of parking area or zone.
4. Refer Sheet TSD-R23 for sign installation details.
5. Refer AS.2890.5-1993 for parallel and angled parking bay setout unless specified on the project drawings.


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R24-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited. It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




Local Government Association Tasmania

STANDARD DRAWING
LINE MARKING
PARKING CONTROL AND SIGNAGE


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-R24-v1



GUIDE POST
SCALE 1 : 10



TYPICAL GUIDE POST LOCATIONS
N.T.S.

TABLE 1

CURVE RADIUS (m)	SPACING (m)	
	OUTSIDE OF CURVE	INSIDE OF CURVE
< 100	6	12
100 – 199	10	20
200 – 299	15	30
300 – 399	20	40
400 – 599	30	60
600 – 799	40	60
800 – 1199	60	60
1200 – 2000	90	90
> 2000 Incl. straights	150	150

NOTES

- Locations for straight sections
 - Spacing of guide posts shall generally be 150m with the posts in pairs (i.e. One each side of the road). Reduce the spacing to 60m in areas subject to frequent fog.
- Locations (Horizontal Curves)
 - Refer Table 1 for spacing of guide posts on curves.
 - Locate first post at the tangent point (T.P.) – Refer plan.
 - Posts on the inside of a curve shall be located opposite posts on the outside of the curve, wherever practicable, commencing at the tangent point.
- General
 - Refer to 'Part 8 Austroads–Traffic Management. (2008)' for further details as required.
- Guide posts to be erected at culverts endwalls.



SCALES: AS SHOWN
(All scales are correct at A3)

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




STANDARD DRAWING
GUIDE POSTS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.

TSD-R25-v1


XRef File: TSD-R25-v1.dwg



TYPE 2

SAFETY BARRIER

(Only Type 2 delineators used on Safety Barrier)



NEW JERSEY BARRIER

(Only Type 2 delineators used on New Jersey Barrier)

INSTALLATION

ROAD TYPE	DELINEATOR TYPE	COLOUR	
		LEFT	RIGHT
one way	1	red	white
two way	1	red	white
one way	2	red	yellow
two way	2	red	white


SPACING

SAFETY BARRIER – Delineators required on tangent point post of flare, then in accordance with table:

ROAD CURVATURE	GUARD FENCE TYPE	
	STEEL BEAM	POST & CABLE
Straight or radius > 300m	32m	33m
Radius from 150m – 300m	20m	21m
Radius < 150m	8m	7.5m or 9m


NOTE – Spacings to be halved for Type 1 delineators installed on curved surfaces.

GUIDE POSTS – Delineators required on all guide posts.



26g G.I. delineator backing plate fixed to posts.

TYPE 1



TYPE 2

DELINEATORS

TYPE 1 – Pressure sensitive retroreflective material in accordance with Class 1A, AS1906. 200x50 on reboundable guide posts.

TYPE 2 – Corner cube reflector Type A, AS1906.

GUIDE POSTS

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R26-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING


DELINEATORS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No.

TSD-R26-v1



EXAMPLES
 1. 10000 A.A.D.T. 100 km/hr
 Clear Zone = 9m
 2. 1500 A.A.D.T. 75 km/hr
 Clear Zone = 4m


In low speed urban environments, a minimum clear zone 1.0m wide may be accepted to achieve an appropriate balance between traffic safety and other aesthetic considerations.

* A.A.D.T. - Average Annual Daily Traffic (Two way)


FIGURE 1

NOTES

- The clear zone is measured from the edge of the traffic lane. Shoulders and verge areas are included as part of the clear zone.
- The desirable clear zone widths should be doubled on the outside of curves with a radii of 600m or less, and when measuring clear zones the width of embankment slopes greater than 3 : 1 should not be included.



JOINT DETAIL
N.T.S.



ELEVATION
SCALE 1 : 25

NOTES

- Treated pine to comply with 'AS.1604-1997' (Timber - Preservative Treated - Sawn and Round)

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R27-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited. It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
CLEAR ZONE
TREATED PINE FENCE


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R27-v1




ELEVATION
SCALE 1 : 25



TYPICAL SECTION
SCALE 1 : 25




**INSTALLATION
(BETWEEN KERB AND RETAINING WALL)**
SCALE 1 : 25



	REFERENCE SURFACE		
	X	Y	Z
Type KC	≤ 150mm	-	700
Type KC	> 3.0m	700	-
Type KCM	2.5m	700	-

**INSTALLATION
(ADJACENT TO KERB)**
SCALE 1 : 25



**INSTALLATION
(ADJACENT TO SHOULDER)**
SCALE 1 : 25



NOTES

1. Refer to Austroads AGRD-10 Part 6: Roadside Design, Safety and Barriers
2. Hot dip galvanise all components.
3. The design for the retaining wall shall make provision for the support requirements of the guard rail.

SCALES: AS SHOWN
(All scales are correct at A3)

REFERENCES

XRef File: TSD-R28-v1.dwg

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




Local Government Association Tasmania

STANDARD DRAWING
W-BEAM
INSTALLATION DETAILS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R28-v1




NOTE:
 1. Blockout and backing plate omitted from first intermediate post.
 2. Cable to be installed taut.

LEADING FLARE

TRAILING FLARE 2 WAY TRAFFIC						
	80m RADIUS			40m RADIUS		
DISTANCE FROM TANGENT POINT (m)	2.0	4.0	6.0	8.0	10.5	13.1
OFFSET TO FACE OF FENCE FROM EDGE OF SHOULDER (m)	0.025	0.100	0.225	0.401	0.8	1.2



TRAILING FLARE – INSIDE CLEAR ZONE



TRAILING FLARE SINGLE DIRECTION TRAFFIC AND OUTSIDE CLEAR ZONE				
	80m RADIUS		40m RADIUS	
DISTANCE FROM TANGENT POINT (m)	2.0	4.0	6.5	9.1
OFFSET TO FACE OF FENCE FROM EDGE OF SHOULDER (m)	0.025	0.100	0.25	0.5

* Post part of standard installation.
 ** Leading flare as for 2 way traffic.

NOTE: -
 Timber posts may be replaced with proprietary steel slip base posts. Refer 3402-4/P69

Department of Infrastructure, Energy and Resources

Standard Drawing No: 3402-4 / P68-5

www.transport.tas.gov.au/road/specifications

SCALES: AS SHOWN
 (All scales are correct at A3)

XRef File: TSD-R29-v1.dwg

REFERENCES

©2012
 This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
 It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au

TAS Division


INSTITUTE OF PUBLIC WORKS ENGINEERING AUSTRALIA

Local Government Association Tasmania

STANDARD DRAWING
 W-BEAM
 TERMINAL TREATMENT

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
 T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013 DWG No. TSD-R29-v1



	80m Radius				Straight
Distance from tangent point	2.0	4.0	6.0	8.0	16.0
Offset from straight	0.025	0.100	0.225	0.401	1.200

FLARE ON EMBANKMENT

SCALE 1 : 100



Distance from tangent point	2.0	4.0	6.0	8.0	10.0	12.0	14.0	16.0	18.0	20.0
Offset from straight	0.040	0.160	0.361	0.644	1.010	1.461	2.000	2.629	3.352	4.174

FLARE IN CUTTING

SCALE 1 : 100



NOTES

1. Refer to Austroads AGRD-10 Part 6: Roadside Design, Safety and Barriers
2. Flare may be required on one or both ends of guard rail installation (Refer construction drawings).
3. Guard rail to be maintained at a constant height above finished surface through to cut batter.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R30-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
W-BEAM
APPROACH / DEPARTURE FLARES


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R30-v1




**TYPE F
(FIXED)**
1 : 10



**TYPE R
(REMOVEABLE)**
1 : 10



COVER PLATE
1 : 10



**COVER PLATE FIXING DETAIL
(TYPE R SHOWN)**
1 : 5



NOTES

1. All bollards may be modified to utilise the various footing options. Only use the 'Base Plate' option on concrete paved areas.
2. Welds – 5mm continuous fillet, unless noted otherwise.
3. Bollard finishes
 - Surface preparation (typical)
 - Galvanised – Section (typical)
 - Powder Coating – Complying with AS.4506 / AS.3715.
 - Paint – 1 Coat zinc rich epoxy primer.
 - 1 Coat external epoxy (gloss) top coat.
 - Specify colour to AS.2700.


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R31-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING
BARRIERS / GUARD RAIL
RIGID BOLLARDS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013


DWG No.

TSD-R31-v1


Aluminium Top fixed with 4 x M5 x 20 lg countersunk s.s. screws.



TYPE L (LOCKABLE)
(Padlock by Others)
1 : 10




ALUMINIUM TOP (CAST)
(‘D’ to suit press fit in 125 NB Bollard)
1 : 5




(12mm M.S. Plate)
BOLLARD BASE – TYPE L


3 x 65 x 65 x 5 EA
Provide 2mm clearance all round to inside of RHS




(All welds 5mm fillet x25 lg at 100 crs)
FIXING BOX INSERT
1 : 5



LOCKING TAB



(12mm M.S. Plate)
HINGED LOCKING PLATE – PLAN



(12mm M.S. Plate)
FIXING BOX – PLAN
(LOCKING PLATE REMOVED)

NOTES

- All bollards may be modified to utilise the various footing options.
- Welds – 5mm continuous fillet, unless noted otherwise.
- Bollard finishes
 - Surface preparation (typical)
 - Galvanised – Section (typical)
 - Powder Coating – Complying with AS.4506 / AS.3715.
 - Paint – 1 Coat zinc rich epoxy primer.
 - 1 Coat external epoxy (gloss) top coat.
 - Specify colour to AS.2700.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R32-v1.dwg

REFERENCES

©2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au


TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

LGAT
Local Government Association Tasmania

STANDARD DRAWING
BARRIERS / GUARD RAIL
LOCKABLE BOLLARDS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013 DWG No. TSD-R32-v1



STONE RETAINING WALL
SCALE 1 : 10
(Grass Embankment Example)

TABLE 1

HEIGHT (mm)	BASE (mm)
0 - 500	350
500 - 1000	500



STONE PITCHING
SCALE 1 : 10

NOTES

1. Stonework – Sound dolerite or basalt, uniform in appearance and composition
Maximum size 200mm x 250mm (face)
Minimum size 100mm x 50mm (face)
2. Concrete – N25
3. Mortar joint mix – 6 sand, 1 cement, 1 lime – Minimum width 10mm, Maximum width 50mm.
Finish mortar joint 3–5mm below face of stones.
4. Remove concrete / mortar staining from stone surface.
5. Place stones randomly to give a uniform appearance.
6. Provide additional drainage for the stone pitched embankment where the water table is high and / or the embankment material is expansive clay, as directed.
7. Provide pipe alternative to drain 'granular filter' or 'free draining' backfill, as directed.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R33-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
STONE WALLS / ROCK PITCHING


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R33-v1




CAST IN CONCRETE
(OPTION 1)




BASE PLATE
(OPTION 2)



BASE PLATE DETAIL
150 x 80 x 10 M.S. PLATE
N.T.S.



POST KEY
SCALE 1 : 5



STAIRWAY – TYPICAL DETAILS
(‘TYPE HR’ HANDRAIL SHOWN)
N.T.S.

NOTES

1. Maximum of 36 treads in one direction.
2. Minimum stairway width – 1.0m, (900 mm clearway).
3. Delete intermediate footings for less than ten treads between landings.
4. Handrails
 - Handrails required both sides for stairways > 2.0m wide.
 - Pipe bends – R 250 unless noted.
 - Top rail and posts – 40 NB. G.S.T. 2.3 W.T.
 - Intermediate rails – 32 NB. G.S.T. 2.0 W.T.
5. Clean up all welds and remove sharp edges prior to painting with two coats of zinc rich paint.
6. Design to comply with current BCA requirements.




TABLE 1

DIMENSION	MINIMUM	MAXIMUM
G	250*	355
R	115	190
2R+G	550	700

* Desirable min. tread width – 300mm.


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R34-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
STAIRWAY CONSTRUCTION


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-R34-v1





TYPE CM – PEDESTRIAN FENCE



**TYPE HRM – HAND RAIL
(TYPE HR – WITHOUT MID RAIL)**



TYPE WRT – PEDESTRIAN FENCE
DIMENSION 'H' – SPECIFIED IN PROJECT DRAWINGS (900 / 1200)



CYCLE REST RAIL

NOTES

- Posts
 - Top / bottom rails and posts – 40 NB. G.S.T. 2.3 W.T. unless noted.
 - Mid rails and intermediate posts – 32 NB. G.S.T. 2.0 W.T. unless noted.
 - Clean up all welds and remove sharp edges prior to painting with two coats of zinc rich paint.
 - Do not use galvanised split fittings for hand railing in road reserves.
- Footings
 - All footings – 250mm diameter N20 concrete.
 - End posts – 600mm deep.
 - Intermediate posts – 450mm deep.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R35-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
PEDESTRIAN FENCES

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013 DWG No.

TSD-R35-v1




ADVANCED TREE (SEALED AREAS)
SCALE 1 : 20

50 x 50 x 2700 HW stakes (3) equally spaced (clear of root ball and branches) with hessian tie above first branching
OR
Galv. / S.S. guy wires fixed with ground anchors, flush with surface and clear of root ball. Cover wires with soft hose pipe where looped around tree trunk



ADVANCED TREE (NON-SEALED AREAS)
SCALE 1 : 20



SMALL PLANTS / SHRUBS (100 – 450mm pots)
SCALE 1 : 10

Min. 100 thick x 1500 dia. mulch kept clear of stem

Liase with local council arborist regarding the need for flexible root control barrier adjacent to service pipes.

Key

- Slow Release Fertiliser
- ⊠ Planting mix

- NOTES**
- Liase with superintendent where clay or ground water is encountered during excavation of planting hole.
 - Tree Supports
 - Trees ≤ 3.0m high – use stakes
 - Trees > 3.0m high – use guy wires
 - Place plants upright and in centre of hole.



SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-R36-v1.dwg

REFERENCES

©2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au

TAS Division


IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

LGAT
Local Government Association Tasmania

STANDARD DRAWING
TREE / SHRUB PLANTING

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013 DWG No. TSD-R36-v1



PLAN
N.T.S.

TABLE 1

PIPE DIAMETER	ANCHOR BLOCK WIDTH
≤ 450	Pipe diameter + 150 mm
> 450	Design required



SECTION A-A
N.T.S.

NOTES

- Construct anchor blocks where pipe grades exceed $\geq 10\%$ at
 - 9.6m centres for Concrete pipes
 - 12.0m centres for P.V.C. pipes
- Landslip areas – site specific design required to ensure land stability risk is not increased.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW01-v1 .dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
PIPE INSTALLATION
ANCHOR BLOCKS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.

TSD-SW01-v1




INTERNAL DROP



EXTERNAL DROP


SECTION A-A




TYPE B - OFFSET SURROUND

MANHOLE SHAFT DIAMETER		
DIA.	DEPTH (m)*	COMMENT
1050	≤ 4.0	Minimum diameter
1200	> 4.0	Less confined
≥ 1200	ALL	To suit multiple pipe configuration

* Depth - F.S.L. to invert



TYPE A - TAPER TOP
INTERNAL DROP



SECTION B-B

NOTES

- Insitu concrete - N25
- Drop Connections For Stormwater Manholes
 - Pipe dia. ≤ 150 - Internal, > 150 - External.
 - Internal drops not permitted for inlet grades > 10.0%
 - Drops > 2.0m - support pipes with 50 x 3 galv. M.S. brackets.
- Stormwater Manholes
 - Joints - apply epoxy / non-shrink grout to form water tight joint.
 - Internal surfaces - remove mortar or concrete splashes and fill all air pockets and cavities with grout.
 - Lid surround - fully ram with N20 grout.
- Access Covers
 - Position access cover on the downstream side of MH.
 - Lightly grease lid contact surface.
 - Refer 'AS.3996-1992' for additional requirements.
- Backfill around manholes - as specified for pipeline.

ACCESS COVER - REFER 'AS.3996-1992'			
DRAIN TYPE	MARKING	LOCATION	
		Trafficable	Non Trafficable
Stormwater	SW	Class D (Sealed)	Class B (Unsealed)*

* Use sealed lids in CBD and other shopping precincts (Sewer and Stormwater)

MANHOLES		
DEPTH	TOP TYPE	LOCATION
≤ 1200	H.D. Offset highway	Road pavement
		Other
1200 >	Taper top	Road pavement
	H.D. Offset highway	Other
	Taper top	

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW02-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
MANHOLES - 100 TO 600 DIA. PIPES
GENERAL ARRANGEMENTS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.


TSD-SW02-v1




SECTION A-A




SECTION B-B




SECTION C-C



PLAN
MANHOLE
(STRAIGHT THROUGH)



PLAN
MANHOLE
(CHANGE IN DIRECTION)



SETOUT REFERENCES

MINIMUM FALL REQUIRED THROUGH SW MANHOLES

DIRECTIONAL CHANGE	H (mm)
0° - 25°	10
26° - 90°	40
91° - 120°	70

NOTE

- Benching
 - Concrete grade - N25
 - Finish - Steel troweled

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW03-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
MANHOLES 100 - 600 DIA. PIPES
BENCHING DETAILS


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW03-v1




SECTION A-A




SECTION D-D




SECTION C-C




DETAIL A




SECTION B-B




DETAIL C




ELEVATION




DETAIL B



HINGE PIN



PLAN
GRATE



PLAN
FRAME
(Hinge pin not shown)

NOTE
1. Hot dip galvanise after fabrication.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW04-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited. It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




Local Government Association Tasmania


STANDARD DRAWING
SIDE ENTRY PITS
GRATE AND FRAME DETAILS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013
DWG No. TSD-SW04-v1



SECTION A-A
(OUTLET PIPE SHOWN IN FULL)



SECTION B-B



PLAN

TABLE 1

Recommended Pit Sizes	
'A'	'B'
450	450
600	600
650	650
750	750
800	500
900	600
900	750
900	900
1200	1200
1225	450
1225	570
1260	450
1350	900
1550	900

Note: Internal dimensions.

NOTES

- Concrete – N25 grade.
- Minimum grade for outlets 1 in 100.
- Refer Sheets:
 - Hydraulic capacity curves in reference area.
 - TSD-SW04 for grate details
 - TSD-SW07, TSD-SW08, TSD-SW09 and TSD-SW10 for lintel details.
- Equivalent pre-cast componentry may be substituted with the approval of the General Manager's delegated officer.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW05-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
SIDE ENTRY PITS - 'SEP'
CONSTRUCTION (CAST IN SITU)


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW05-v1




PLAN
(KERB AND LINTEL NOT SHOWN)
SCALE 1 : 25



SECTION B-B
SCALE 1 : 25



SECTION A-A
(BAR NOT SHOWN)
SCALE 1 : 25



TYPICAL SECTION
FLUSHING POINT COVER
AND SURROUND DETAIL
N.T.S.

NOTES

1. Concrete – N25 grade.
2. Minimum grade for outlets 1 in 100.
3. Transition kerb depth from 140 – 190mm.
4. Fit lintels with 20 dia. rod.
5. Refer Sheets:
 - TSD-SW04 for grate details
 - TSD-SW07, TSD-SW08, TSD-SW09 and TSD-SW10 for lintel details
6. Pre-cast manufacturer option available manufacturers specification to meet LGAT standards

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW06-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013


DWG No.

TSD-SW06-v1


STANDARD DRAWING
SIDE ENTRY PITS - 'SEPS'
CONSTRUCTION (COMBINE AREAS ONLY)




SECTION A-A
(20 Dia. galv. rod not shown)



SECTION B-B



PLAN



PRECAST LINTEL (SECTION)

NOTES

1. Concrete – N25 grade.
2. Refer Sheets:
 - TSD-SW04 for grate details
 - TSD-SW05 for unsealed pit construction
 - TSD-SW06 for sealed pit construction
 - TSD-SW11 for kerb transitions
3. Pre-cast manufacturer option available manufacturers specification to meet LGAT standards

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW07-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
SIDE ENTRY PITS
'TYPE 1'

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.


TSD-SW07-v1




SECTION A-A
(20 Dia. galv. rod not shown)



SECTION B-B



PRECAST LINTEL (SECTION)



PLAN

NOTES

- Concrete – N25 grade.
- Refer Sheets:
 - TSD-SW04 for grate details
 - TSD-SW05 for unsealed pit construction
 - TSD-SW06 for sealed pit construction
 - TSD-SW11 for kerb transitions
- Pre-cast manufacturer option available manufacturers specification to meet LGAT standards


SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW08-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania




STANDARD DRAWING
SIDE ENTRY PITS
'TYPE 2'

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No.

TSD-SW08-v1



NOTES

1. All dimensions in millimetres (mm)
2. Precast components encouraged where available.
3. Angle lintel to be hot dipped galvanised mild steel.
4. Max. depth to be 1500mm – dictated by cover
5. Pits can be used for change of pipe grade or direction where suitable hydraulic conditions exist.
6. Pit to be constructed from N25 concrete.
7. Pre-cast manufacturer option available manufacturers specification to meet LGAT standards

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW09-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING

SIDE ENTRY PITS


'TYPE 3'

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au




ISSUE DATE: 30-11-2013


DWG No.

TSD-SW09-v1




- NOTES**
1. All dimensions in millimetres (mm)
 2. Precast components encouraged where available.
 3. Angle lintel to be hot dipped galvanised mild steel.
 4. Max. depth to be 1500mm – dictated by cover
 5. Pits can be used for change of pipe grade or direction where suitable hydraulic conditions exist.
 6. Pit to be constructed from N25 concrete.
 7. Equivalent pre-cast componentry may be substituted with the approval of the General Manager's delegated officer.







TYPE KCS



TYPE KCM



TYPE BK



TYPE PCM

NOTES

1. Line inverts up through plan transition.
2. Refer Sheets:
 - TSD-SW07, TSD-SW08, TSD-SW09
 - TSD-SW10 for lintel details

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW11-v1.dwg

REFERENCES

TSD-SW11-v1

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
SIDE ENTRY PITS
KERB TRANSITIONS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.



TSD-SW11-v1




SECTION B-B




LINTEL (GALV. M.S. ANGLE)




SECTION A-A



Standard 600 mm heavy duty 'Gatic' (or approved equivalent) lid and surround integrally cast into pit top.



PLAN (CUT AWAY VIEW)



PRE-CAST PIT TOP

NOTES

1. Lap (300) all reinforcing with min. 50mm cover. (U.N.O.)
2. Provide 20mm chamfer for all exposed edges.
3. Concrete strength N25, min. 150mm thick.
4. 'PCM' - Precast mountable kerb.
5. Refer Sheets:
 - TSD-S04 for grate details
 - TSD-S05 for unsealed pit construction
6. Equivalent pre-cast componentry may be substituted with the approval of the General Manager's delegated officer.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW12-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
SIDE ENTRY PITS
'TYPE 5'


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW12-v1




SECTION A-A
(Bar removed for clarity)



SECTION B-B



PLAN



PICTORIAL VIEW

NOTES

1. Position chequer plate on side of maximum flow.
2. Provide 20 radius on all exposed edges of in-situ poured concrete.
3. Vary wingwall channel crossfall to suit table drain.
4. Concrete – N25 grade, 150 thick.
5. Fit lintels with 20 dia. galv. rod.
6. Refer Sheets:
 - TSD-SW04 for grate details
 - TSD-SW05 for unsealed pit construction

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW13-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division






Local Government Association Tasmania

STANDARD DRAWING
SIDE ENTRY PITS
TABLE DRAIN PIT CONSTRUCTION

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au




ISSUE DATE: 30-11-2013

DWG No. TSD-SW13-v1



NOTES

1. All dimension in millimetres (mm)
2. Pit to be constructed from grade N25 concrete.
3. All bars and angles to be grade 250 mild steel.
4. Equivalent pre-cast componentry may be substituted with the approval of the General Manager's delegated officer.




SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW14-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA





STANDARD DRAWING
STORMWATER - 'GVP'





GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No. TSD-SW14-v1



Grate and frame must be bicycle safe and structurally in accordance with AS 3996.



NOTES

1. All dimension in millimetres (mm)
2. Pit to be constructed from grade N25 concrete.
3. All bars and angles to be grade 250 mild steel.
4. Pre-cast manufacturer option available manufacturers specification.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW15-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
STORMWATER - 'GP'


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013


DWG No. TSD-SW15-v1




SECTION A-A




SAG PIT DETAILS




SECTION B - B




ON GRADE PIT DETAILS



SECTION C - C



GRATE DETAIL



DETAIL A

NOTES

1. All concrete to have a minimum strength of N25.
2. Clean cement stabilised sand to be compacted under kerb transitions.
3. Mass concrete, 150mm minimum, to be placed under lintel.
4. Standard manhole shaft to be $\phi 1050$ RCP
5. All grate and frame components to be hot dipped galvanised.
6. Refer TSD-SW04-v1.
7. Pre-cast manufacturer option available manufacturers specification.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW16-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




Local Government Association Tasmania

STANDARD DRAWING
SIDE ENTRY PITS
'TYPE 6'


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW16-v1





ELEVATION



SECTION B-B



PLAN DOUBLE ENDWALL



SECTION A-A

DIMENSION TABLE

PIPE DIAMETER	300	375	450	525	600	675	750	825	900
HEADWALL DIMENSIONS (mm)									
A1	1425	1600	1750	1950	-	-	-	-	-
a	150	150	150	150	175	175	200	200	225
b	300	300	300	300	375	375	400	400	425
c	300	300	300	300	350	350	350	350	350
d	375	375	375	375	530	530	530	530	530
e	150	150	150	150	175	175	200	200	225
f	75	75	75	75	100	100	100	100	100
g	40	40	40	40	50	50	50	50	50
h	70	70	70	70	75	75	100	100	125
j	200	200	200	200	300	300	300	300	300
w	700	700	850	1000	1100	1300	1450	1600	1750
Vol. of concrete (m ³)	0.329	0.375	0.485	0.621	0.981	1.220	1.483	1.702	2.027
Reinforcing (all bars N12)									
L - (Rear)	845	921	1017	1099	1204	1287	1388	1470	1575
L - (Front)	803	880	975	1057	1140	1223	1305	1387	1471
Reo. Length (mm)	1648	1801	1992	2156	2344	2510	2693	2857	3046
Reo. Mass (kg) *	1420	1509	1687	1776	1954	2131	2220	2398	2486

* Does not include SL82 mesh to slab

NOTES

1. Quantities are for one headwall only.
2. Provide 12mm chamfer for all exposed surfaces.
3. Concrete grade - N25.
4. Pre-cast manufacturer option available manufacturers specification.
5. All dimensions in millimetres (mm)
6. Provide rock pitching as directed by General Manager's delegated officer.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW17-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
OUTLET HEADWALLS
300 TO 900 DIA. PIPES


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW17-v1





ELEVATION



SECTION B-B



SECTION C-C



SECTION A-A

DIMENSION TABLE

PIPE DIAMETER	1050	1200	1350
HEADWALL DIMENSIONS (mm)			
a	450	450	530
b	1380	1550	1700
w	1930	2300	2500

BAR SHAPE (ALL BARS N12)	MARK	1050 DIA. PIPE					1200 DIA. PIPE					1350 DIA. PIPE				
		L1 mm	L2 mm	L1+L2 mm	No. Req'd	Total Length	L1 mm	L2 mm	LG mm	No. Req'd	Total Length	L1 mm	L2 mm	LG mm	No. Req'd	Total Length
	A1	1404	-	1404	2	2.81	1587	-	1587	2	3.17	1486	-	1486	2	2.97
	A2	1967	-	1967	2	3.93	2340	-	2340	2	4.68	2127	-	2127	2	4.25
	A3	-	-	-	-	-	-	-	-	-	-	2537	-	2537	2	5.07
	B1	781	250	1031	2	2.06	765	250	1015	2	2.03	845	300	1145	2	2.29
	B2	1967	250	2217	4	8.87	2340	250	2590	4	10.36	2537	300	2837	4	11.35
	C1	1259	750	2759	2	5.52	1412	750	2912	2	5.82	1565	750	3065	2	6.13
	C2	1392	750	2892	2	5.78	1545	750	3045	2	6.09	1698	750	3198	2	6.40
	C3	1649	2095	5839	1	5.84	1802	2465	6732	1	6.73	1955	2665	7285	1	7.29
	D1	629	-	1329	2	2.66	641	-	1341	2	2.68	790	-	1490	2	2.98
	D2	-	-	-	-	-	751	-	1451	2	2.90	930	-	1630	2	3.26
	D3	774	-	1474	2	2.95	860	-	1560	2	3.12	1071	-	1771	2	3.54
	D4	918	-	1618	2	3.24	970	-	1670	2	3.34	1211	-	1911	2	3.82
	D5	1062	-	1762	2	3.52	1080	-	1780	2	3.56	1351	-	2051	2	4.10
	D6	1207	-	1907	2	3.81	1189	-	1889	2	3.78	1492	-	2192	2	4.38
	D7	1352	-	2052	2	4.10	1299	-	1999	2	4.00	1632	-	2332	2	4.66
	D8	1496	-	2196	2	4.39	1408	-	2108	2	4.22	1773	-	2473	2	4.95

Reo. Mass = 52.81 kg *	Reo. Mass = 59.03 kg *	Reo. Mass = 68.77 kg *
Volume of concrete (2.794 m3)	Volume of concrete (3.499 m3)	Volume of concrete (3.987 m3)

* Does not include SL82 mesh in apron.

NOTES

- Quantities are for one headwall only.
- Chamfer (10 x 10) all exposed surfaces.
- Concrete grade - N25.
- Cover to all reinforcing 50mm unless noted.
- Pre-cast manufacturer option available manufacturers specification
- All dimensions in millimetres (mm)
- Provide rock pitching as directed by General Manager's delegated officer.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW18-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA



Local Government Association Tasmania

STANDARD DRAWING
OUTLET HEADWALLS
1050 TO 1350 DIA. PIPES

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No. TSD-SW18-v1






TABLE 1

NOMINAL PIPE DIAMETER	HEADWALL DIMENSIONS (mm)	
	A1	A2
300	1150	1850
375	1350	2100
450	1550	2400
525	1750	2650

NOTES

1. Quantities are for one headwall only.
2. Chamfer (10 x 10) all exposed surfaces.
3. Concrete grade – N25.
4. Cover to all reinforcing 50mm unless noted.
5. Equivalent pre-cast componentry may be substituted with the approval of the General Manager's delegated officer.
6. Lap reinforcement 300 min.
7. All dimensions in millimetres (mm)
8. Provide rock pitching as directed by General Manager's delegated officer.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW19-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
CONCRETE ENDWALL PLAIN
(300 - 450 DIA)

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.


TSD-SW19-v1



PLAN



SECTION A-A



FRONT ELEVATION

TABLE 1

NOMINAL PIPE DIAMETER	HEADWALL DIMENSIONS (mm)			
	a	b	c	d
300	365	550	600	800
375	450	600	675	900
450	538	650	750	1000

NOTES

1. All dimensions in millimetres (mm)
2. Stone headwall to be used only where the specific approval of the General Manager's delegated officer.
3. All stones to be set in mortar consisting of 1 part cement to 3 parts clean sand.
4. All stones to be clean, hard and durable and shall have weight of between 10 & 70kg.
5. All stones shall have a length of at least 1.5 times the width and shall be bedded to the course below on their broadest base.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW20-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division




Local Government Association Tasmania

STANDARD DRAWING
OUTLET HEADWALLS
GROUTED STONE (300 - 450 DIA)


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW20-v1




INLET GRATE
FRONT ELEVATION



DETAIL B



SECTION A-A



INLET GRATE
PLAN

(Headwall to suit 750 dia. pipe shown)

DIMENSION TABLE

HEADWALL SIZE	DIAMETER			
	300, 375, 450	525, 600	675, 750	900
'L' (mm)	1600	2030	2600	3425
'D' (mm)	26.9 O.D. x 3.2 W.T.	33.7 O.D. x 4 W.T.	42.4 O.D. x 4 W.T.	48.3 O.D. x 4 W.T.
'A' (mm)	40 x 40 x 5	45 x 45 x 5	55 x 55 x 5	65 x 65 x 5

O.D. = Outside Diameter
W.T. = Wall Thickness

FIXING DETAILS

Headwall Size	Galv. Masonry Anchors	No. required
300, 375, 450	M10 - 50mm embedment	4
525, 600	M10 - 50mm embedment	4
675, 750	M10 - 50mm embedment	6
900	M10 - 50mm embedment	8

NOTES

1. This drawing is for new installations.
Inlet grating gradient - 1 in 3.
2. All welds - 5mm fillet all round.
3. Clean up all welds and remove sharp edges prior to hot dip galvanising to 'AS.1650'.
4. Preparation for galvanising - Cut two V's measuring 20 wide x 25 long, out of opposite sides and each end of CHS and RHS sections to facilitate internal galvanising.
5. Headwall for single pipe entry shown. For multiple pipes refer to local council. General Manager's delegated officer. for design requirements.
6. Not all hidden detail shown, for clarity.
7. Concrete - N25.
8. Refer Standard drawing TSD-SW17 headwall dimensions.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW21-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania







STANDARD DRAWING
INLET HEADWALLS
GRATED INLET - 300 TO 900 DIA. PIPES

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE:
30-11-2013

DWG No.

TSD-SW21-v1



NOTES


1. Clean up all welds and remove sharp edges.
2. Hot dip galvanise grate after fabrication.
3. All welds 3.0 mm continuous fillet.
4. Preparation for galvanising – Cut two V's measuring 20 wide x 25 long, out of opposite sides and each end of CHS and RHS sections to facilitate internal galvanising and cut hole in Post Plate for CHS post.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW22-v1.dwg

REFERENCES


©2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au




STANDARD DRAWING
INLET HEADWALLS (SQUARE)
RAISED GRATED INLET

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No. TSD-SW22-v1




DOMED INLET GRATE
PLAN



ELEVATION

NOTES

1. Clean up all welds and remove sharp edges.
2. Hot dip galvanise grate after fabrication.
3. All welds 3.0 mm continuous fillet.
4. Preparation for galvanising – Cut two V's measuring 20 wide x 25 long, out of opposite sides and each end of CHS and RHS sections to facilitate internal galvanising and cut hole in Post Plate for CHS post.



2-Dia 14 holes for masonry anchors plus
1-Dia 14 drain hole in centre of plate.

SECTION AA

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW23-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA




Local Government Association Tasmania

STANDARD DRAWING
INLET HEADWALLS (DOMED)
RAISED GRATED INLET


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013 DWG No.


TSD-SW23-v1




Where 'D' is $\geq 300 \phi$ – Grate all Inlet Headwalls



Where 'D' is $\geq 300 \phi$ and $< 900 \phi$ – No Inlet Headwall Grate



Where 'D' is $\geq 300 \phi$ and $< 1200 \phi$ – Grate all Inlet Headwalls



Where 'D' is $\geq 1200 \phi$ – Fence all Headwalls
(Fence – 1200mm high Type 'CM')



Fix both signs to outlet headwalls where 'D' is $> 900 \phi$ and pipe length is $\geq 20m$.

Stormwater Outlet Headwall

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-SW24-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013



DWG No.

TSD-SW24-v1

STANDARD DRAWING HEADWALLS INLET GRATE AND FENCE REQUIREMENTS




ELEVATION




PLAN

TYPICAL OBLIQUE BRANCH CONNECTION
(MAIN LOCATED OUTSIDE BOUNDARY)



ELEVATION




PLAN


TYPICAL JUMP CONNECTION

NOTES

1. Pipe bedding and backfill in accordance with Standard Drawing TSD-G01
2. Jump up to be used on all stormwater connections deeper than 2.0m.
3. Survey completed main by CCTV and submit report by DVD. (All new sub-division installation)



MAIN IN ROAD RESERVE



MAIN IN PRIVATE PROPERTY

MAINTENANCE RESPONSIBILITY

- Local Council
- Property Owner

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW25-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING


STORMWATER PROPERTY CONNECTIONS TO MAINS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.


TSD-SW25-v1



ELEVATION



SECTION A-A
(C.S.S.D. AND DOLLY NOT SHOWN)



PLAN

NOTES

CASE 1 – P.V.C. SADDLE TO 160 O.D. POLY MAIN.

- ① 160 O.D. Poly main.
- ② Glue 75mm long piece of 150 dia. P.V.C. pipe into female socket. Cut down 45° 150 x 100 P.V.C. reducing junction.
- ③ Use inside of reducer as a template to mark poly main. Cut and remove sharp edges.
- ④ Check 102mm O.D. M.S. exhaust tubing dolly can be inserted approximately 280mm through 45° junction into main. Clean both mating surfaces.
- ⑤ Apply minimum 2 x 4mm continuous bead of Selleys 'Wet Seal' (Silicon) or similar 10mm from edge and 10mm apart.
- ⑥ Insert dolly into main, slide junction down onto silicon beads.
- ⑦ Clamp with 2 x 13mm stainless steel worm drive hose clamps both ends. Fully wrap clamps both ends with denso tape. Remove dolly.
- ⑧ Support/encase connections with cement stabilised stone dust (3% cement) minimum 500mm long 300mm wide x 300 deep.

CASE 2 – P.V.C. SADDLE TO P.V.C. MAIN.

- ① Existing 150 dia. P.V.C. main.
- ② Glue 75mm long piece of 150 dia. P.V.C. pipe into female socket. Cut down 45° 150 x 100 P.V.C. reducing junction.
- ③ Use inside of reducer as a template to mark P.V.C. main. Cut and remove sharp edges.
- ④ Check 102mm O.D. M.S. exhaust tubing dolly can be inserted approximately 280mm through 45° junction into main. Clean both mating surfaces.
- ⑤ Apply solvent cement to mating surfaces.
- ⑥ Insert dolly into main, slide junction down onto solvent cement.
- ⑦ Clamp with 2 x 13mm stainless steel worm drive hose clamps both ends. Fully wrap clamps both ends with denso tape. Remove dolly.
- ⑧ Support/encase connections with cement stabilised stone dust (3% cement) minimum 500mm long 300mm wide x 300 deep.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW26-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING


SADDLE CONNECTION TO STORMWATER DRAIN

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE:
30-11-2013

DWG No.

TSD-SW26-v1





**TYPICAL JUNCTION BRANCH
ENTRY ALIGNMENT**




ENLARGED CUT-AWAY VIEW


- NOTES**
1. New service connections may be installed by Council or by Contractor supervised by Council.
 2. 'Flashcrete' – quick setting cementitious mortar or similar.
 3. Refer Sheet TSD-G01 for additional trench backfill detail.




**ELEVATION
150 DIA. EW CONC.**




**ELEVATION
≥ 300 DIA. EW / CONC**




**TYPICAL JUNCTION BRANCH
ENTRY ALIGNMENT**




**ELEVATION
225 & 300 DIA. EW CONC.**




FLOW CONNECTION JUNCTION BRANCH




PICTORIAL VIEW




PICTORIAL VIEW



SECTION A-A
TYPE SC1
SILT FENCE AT GRATED PIT



SECTIONAL VIEW
TYPE SC3
SILT FILTER AT GULLY PIT



TYPE SC2
SILT FENCE FOR PIPELINE CONSTRUCTION

NOTES

SILT FENCE – 'TYPES SC1 AND SC2'

1. Construct as detailed and install 'Class A' geotextile or use proprietary silt fence.
2. Omit sandbag wall and silt trap when pit is in a low point.

GULLY PIT FILTER – 'TYPE SC3'

3. Galv. wire mesh 2mm dia. x 12mm opening.

GENERAL

4. Clear sediment after each storm.
5. 'Type SC2' can also be used for maintenance or connection of services to existing pipelines.

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-SW28-v1.dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING
GUIDELINES FOR SEDIMENT CONTROL

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au


ISSUE DATE: 30-11-2013

DWG No.

TSD-SW28-v1

SIGHT DISTANCES

(2 LANE ROAD ONLY)



PLAN




FIGURE 1:

VEHICLE SPEED (km/h)	SAFE INTERSECTION SIGHT DISTANCE METRES, FOR SPEED LIMITS OF:	
	60 km/h or less	Greater than 60 km/h
50	80	90
60	105	115
70	130	140
80	165	175
90		210
100		250
110		290

NOTES:

- For maximum driveway access slopes refer TSD-R04
- The angle of intersection should be between 70° and 90° to the major road.
- Shall be the posted speed limit for assessment of access driveways.
- Refer to AGRD04A – Part 4A Unsignalised and Signalised Intersection.

DEFINITIONS:

Vehicle Speed = Vehicle speed is the actual or recorded speed of traffic passing along the road and is the speed at or below which 85% of passing vehicles travel.

S.I.S.D = Safe Intersection Sight Distance.

- Provides sufficient distance for a driver of a vehicle on the major road to observe a vehicle on a driveway approach moving into a collision situation (e.g. in the worst case, stalling across the traffic lanes) and to decelerate to a stop before reaching the collision point.
- Is viewed between two points to provide inter-visibility between drivers and vehicles on the major road and minor road approaches. It is measured from a driver eye height of 1.1m above the road to points 1.25m above the road which represents drivers seeing the upper part of cars as illustrated on Figure 1.
- Assumes that the driver on the minor road is situated at a distance of 5m (minimum of 3m) from the lip of the channel or edge line projection of the major road. S.I.S.D allows for a 3s observation time for a driver on the priority legs of the intersection to detect the problem ahead, (e.g. car from driveway stalling on through lane) plus the SSD.
- Provides sufficient distance for a vehicle to cross the non-terminating movement on two-lane two way roads, or undertake two-stage crossing of dual carriageways, including those with vehicle speeds of 80 km/h or more.
- Should also be provided for drivers stored in the centre of the road when undertaking a crossing or right-turning movement.
- Enables approaching drivers to see an articulated vehicle, which has properly commenced a manoeuvre from a leg without priority, but its length creates an obstruction.
- Is measured along the carriageway from the approaching vehicle to the conflict point, the line of sight having to be clear to a point 5m (3m minimum) back from the holding line or stop line on the side road.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-RF01-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING GUIDE TO INTERSECTION AND DOMESTIC ACCESS SIGHT DISTANCE REQUIREMENTS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE:
30-11-2013

DWG No.

TSD-RF01-v1

LINE TYPE	CODE	CODE Audio Tactile	PAVEMENT MARKING DETAILS	WIDTH (mm)	TYPICAL APPLICATION
Barrier (One direction)	(B1)	(B1a)		100	Centre lines on higher category two way undivided rural roads.
Barrier (Both direction)	(B2)	(B2a)		100	Centre lines on higher category two way and multi-lane undivided rural roads.
Barrier (Both direction)	(B3)	(B3a)		100	Centre lines on lower category two way undivided rural and urban roads. Dividing line at junctions
Barrier (Both direction)	(B4)	(B4a)		200	Centre lines on multi-lane undivided urban roads. Approach marking to urban traffic islands.
Separation (Rural)	(S)	(Sa)		100	Centre lines in two way undivided rural roads.
Separation (Urban)	(S1)			100	Centre lines in two way undivided urban roads.
Separation (Median lane)	(S2)			100	Definition of median turning lanes
Separation (Social purpose)	(S3)	(S3a)		100	Centre lines where enhanced delineation is required and continuous line is not appropriate.
Separation (Bicycle paths)	(S4)			80	Centre lines on dedicated off-road bicycle paths.
Lane (Rural)	(L)			100	Lane lines on multi-lane rural roads.
Lane (Urban)	(L1)			100	Lane lines on multi-lane urban roads.
Lane (Turnout lane)	(L2)			100	Lane lines at slow vehicle turnouts.
Lane (Special purpose)	(L3)			100	Lane lines on multi-lane roundabouts or where enhanced delineation is required and a continuous line is not appropriate.
Lane (Continuous)	(LC)			100	Lane lines where prohibiting lane change maneuvers is required
Continuity	(C)			200	Entry points to right and left turn facilities. Entry and exit ramp merge/diverge areas.
Continuous Continuity	(CC)	(CCa)		200	Right and left turn facilities. Entry and exit ramp gore areas. Channelising at traffic islands.
Edge (Urban)	(E)			100	Edge lines on urban roads. On-road bicycle lanes.
Edge Continuity (Urban)	(EC)			100	Edge lines continuity on urban roads. Continuity of on-road bicycle lanes past side road junctions.
Edge (Rural)	(E2)	(E2a)		150	Edge lines on rural roads.
Edge Continuity (Rural)	(EC2)			150	Edge lines continuity on rural roads.


LINE TYPE	CODE	MARKING DETAILS	WIDTH (mm)	TYPICAL APPLICATION
Stop	(SL)		300	Intersections/Junctions controlled by Stop signs or traffic signals, Children's crossings.
Holding	(HL)		300	Intersections/Junctions/roundabouts controlled by give ways signs.
Junction (Continuity)	(JC)		150	Where additional definition across the right hand side of an urban junction is required. (Refer Drawing SD-84.001)
Turn (Traffic signals)	(T)		100	Definition of turn maneuvers at traffic signals
Pedestrian Walkway	(W)		100	Definition of pedestrian walkways at traffic signals and children's crossings.
No Stopping (Refer Note 1)	(NS)	(Yellow)	100	Restriction of stopping parking where use of parking control signs is not appropriate.

AUDIO-TACTILE PAVEMENT MARKING DETAILS	
TYPE-A (Typically on asphalt surfaces)	TYPE-B (Typically on asphalt surfaces)
<ul style="list-style-type: none"> 8mm thick thermoplastic strips placed on road surface followed by standard waterborne paint to match specified line type and width. Application over existing painted marking is permitted provided final application of standard waterborne paint is applied following strip placement. 	<ul style="list-style-type: none"> 2mm thick thermoplastic line with 6mm thermoplastic strips integrated on top of base line. 50mm drainage gaps shall be provided in accordance with DIER Specification R64.

NOTES

- All pavement marking shall be white except 'No Stopping' markings which are yellow.
- Setout dimensions for all markings shall be measured to the centre of the line type.
- All dimensions are in metres unless noted otherwise.
- Refer DIER Specifications R64 and T10 for performance and application guidelines.

RESPONSIBILITY



Department of Infrastructure,
Energy and Resources
Transport Division

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-RF02-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING
LINE MARKING TRAFFIC CONTROL

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013


DWG No.

TSD-RF02-v1



HYDRAULIC CAPACITY IN SAG
(1220mm AND 1830mm LINTELS)

Curves based on theoretical calculations.
Use of 1220mm lintels not favoured in sag conditions.



HYDRAULIC CAPACITY ON GRADE
(1220mm AND 1830mm LINTELS AT 3% CROSSFALL)

On grade inlet capture rates based on model studies.
(Refer TSD design file No. JF.95.077)

NOTES

- Maximum flow widths:
 - 0.45m adjacent to pedestrian crossing points and bus stops.
 - 1.00m adjacent to traffic through lanes and in acceleration, deceleration and left turn lanes.
 - 2.50m adjacent to road shoulders and parking lanes.
- Inlet capture rates (Cr) ignores interception by grate (assumed to be blocked by leaves). Assumes 50mm depression, 600mm long transition, 125mm deep throat and trough below the lintel.
- For crossfalls greater than 3% use 3% curves. For 2% crossfalls, reduce capacity by:
 - 25% for 1220 lintel
 - 50% for 1830 lintel
- Refer to 'The University Of New South Wales Water Research Laboratory – Physical Modelling Of Stormwater Side Entry Pits (628.2420994 COX)' for sealed side entry pits.

L = Lintel
Cr = Capture rate
W = Flow width adjacent to kerb

SCALES: AS SHOWN
(All scales are correct at A3)

XRef File: TSD-RF03-v1.dwg

REFERENCES

© 2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania


STANDARD DRAWING

SIDE ENTRY PITS HYDRAULIC CAPACITY CURVES

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No. TSD-RF03-v1



NOTES

Soil Type

- Sandy loam (free of weeds and stones).
- Topsoil – Min. 100mm thick

Preparation Before Sowing

- Light roll prior to sowing and lightly raked after sowing.

Seed Mix

- 70% – blend of two varieties
- 30% – blend of two varieties
- Application rate – 1.0 kg per 30 square metres.

Initial Fertilizing

- A complete fertilizer (8 : 4 : 10 – N : P : K) ratio or similar (e.g. 'Lawn Starter') should be used.
- N : P : K – Nitrogen : Phosphorous : Potassium
- Application rate – 1.0 kg per 33 square metres.

SCALES: AS SHOWN
(All scales are correct at A3)


XRef File: TSD-RF04-v1 .dwg

REFERENCES

©2012

This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.

It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



IPWEA

INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA

TAS Division



Local Government Association Tasmania

STANDARD DRAWING

NATURE STRIP DETAILS

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No.

TSD-RF04-v1

<p><u>BREAK O'DAY COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	<p><u>DEVONPORT CITY COUNCIL</u></p> <ul style="list-style-type: none"> TSD-R02: Table 2 is to be replaced by 'refer to Devonport City Council, Road Network Strategy, Tables 2 & 4'. TSD-R06: Table 1 is to be replaced by 'refer to Devonport City Council, Road Network Strategy, Tables 1 & 3'. 	<p><u>KINGBOROUGH COUNCIL</u></p> <ul style="list-style-type: none"> TSD-G01: Minimum asphalt thickness to be 40mm DG10 or DG14. All trenching under sealed roads to have full depth FCR. TSD-G02: Footpaths to be 1350 to BOK, 1500mm when clear of kerb. For services not in the roadway, cover requirements to be as per service providers requirements. TSD-G03: Minimum offset from public infrastructure to property boundary or easements is 1000mm from the side of the pipe. All clearances are subject to the approval of the Executive Manager Engineering Services. TSD-R01: Face of barrier to be located at the outer edge of the shoulder (also applies to guide posts). Shoulder grades are to be no greater than 10%. TSD-R02: Minimum 1000mm shoulder irrespective of edge line. Shoulder grades to be no greater than 10%. TSD-R03: Seal to property boundary or to a maximum of 6.0m from edge of shoulder. Minimum culvert size DN375. TSD-R04: Minimum culvert size to be DN375. Pipe material and resulting cover requirements to the approval of the Executive Manager Engineering Services. TSD-R05: Minimum culvert size to be DN375. TSD-R06: Width and footpath requirements to be in accordance with the Kingborough Planning Scheme. Footpath to be 1350mm from BOK. Minimum 40mm asphalt wearing course. TSD-R09: Segmental pavers are not approved. Standard grey broom finish for concrete. Minimum driveway width 3000mm. SL82 mesh central. Footpath 1350 to BOK. TSD-R10: Trafficable swale crossings to be to the satisfaction of the Executive Manager Engineering Services. Minimum width 3000mm. SL82 central. TSD-R11: All footpaths to be dowelled to back of kerb. Note 2 W to be 1350mm to BOK. TSD-R12: Location of sub soil drains to be to the satisfaction of the Executive Manager Engineering Services. Pavement design to be undertaken by a suitably qualified and experienced practitioner. TSD-R14: Wedge profiles are not permitted. TSD-R18: Trafficable swale crossings to be to the satisfaction of the Executive Manager Engineering Services. Minimum width 3000mm. SL82 central. TSD-R19: Not applicable to KMC. TSD-R36: Use of engineered soils should be considered/noted when in proximity to kerb or road pavement where compaction or settlement of the 'planting mix' could result in disturbance to levelling strips or pavement. TSD-SW07: Grate type not approved by KMC. TSD-SW08: Grate type not approved by KMC. TSD-SW09: Max depth approved to 1650mm. TSD-SW10: Max depth approved to 1650mm. TSD-SW13: Not approved by KMC.
<p><u>BRIGHTON COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 		
<p><u>BURNIE CITY COUNCIL</u></p> <ul style="list-style-type: none"> TSD-R01: Rural Road unsealed TSD-R02: Rural Road sealed TSD-R06: Urban Roads Typical Section and Pavement Widths TSD-R07: Urban Roads – Cul-de-sac Turning Heads. Road Reservation Width (R) to be approved by the General Managers Delegated Officer. TSD-R08: Typical Cul-de-sac details Urban and Rural. Road Width (W) face of Kerb to Face of Kerb to be approved by the General Managers Delegated Officer. 	<p><u>DORSET COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
	<p><u>FLINDERS COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
	<p><u>GEORGE TOWN COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
	<p><u>GLAMORGAN SPRING BAY COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
<p><u>CENTRAL COAST COUNCIL</u></p> <ul style="list-style-type: none"> TSD-R14: Variation to Standard Kerb Profiles TSD-R15: Variation to Stormwater Kerb Outlets. 	<p><u>GLENORCHY CITY COUNCIL</u></p> <ul style="list-style-type: none"> TSD-R15: Concrete Kerbs and Channels construction details: Use current Glenorchy City Council practice. TSD-R18: Access Ramps: Using current AS1428-2009 	
<p><u>CENTRAL HIGHLANDS COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	<p><u>HOBART CITY COUNCIL</u></p> <ul style="list-style-type: none"> TSD-SW01: Anchor blocks required where pipe grades >20% TSD-RF01: NB Lesser sight distances than detailed may be appropriate for access driveways, but shall be accessed by a suitably qualified practitioner having regard to the requirements of AS2980.1 (Parking facilities Pt1: Off Street Car Parking). TSD-R24: Regulatory parking signage and line marking can only be installed if approved by the Transport Commission (DIER), or a Council Officer with the appropriate delegation under Section 10 of the Transport Act 1981. 	
<p><u>CIRCULAR HEAD COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	<p><u>HUON VALLEY COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
<p><u>CLARENCE CITY COUNCIL</u></p> <ul style="list-style-type: none"> TSD-R07: Urban Roads: Cul-de-sac turning heads to effect that Clarence City Council will only accept circular or offset circular turning heads. 	<p><u>KENTISH COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 	
<p><u>DERWENT VALLEY COUNCIL</u></p> <ul style="list-style-type: none"> No Departures or Exclusions 		

<u>KING ISLAND COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	<u>TASMAN COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	
<u>LATROBE COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	<u>WARATAH-WYNYARD COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	
<u>LAUNCESTON CITY COUNCIL</u> <ul style="list-style-type: none"> Roads: Council wishes to retain the discretion to vary the road standards described in TSD-R01, TSD-R02 & TSD-R06 to allow the pavement width and surface type to be specified by the Planning Permit conditions. 	<u>WEST COAST COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	
<u>MEANDER VALLEY COUNCIL</u> <ul style="list-style-type: none"> TSD-R02: Table 2 needs to align with MVC's road hierarchy TSD-R06: Tables 1 and 2 need to align with MVC's road hierarchy TSD-R18: access ramp Type B: 'footpath' dimension needs an additional 150mm, i.e. the BK kerb should not be included in the overall width of the footpath. TSD-R34: Exclude option 2: MVC will allow posts to be welded directly to cast in situ plates. Detail of plates to be determined by municipal engineer. 	<u>WEST TAMAR COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 	
<u>NORTHERN MIDLANDS COUNCIL</u> <ul style="list-style-type: none"> TSD-R11: Minimum footpath width 1800mm. TSD-R14: The kerb profiles shown on drawing TSD-R14 will not be used in Northern Midlands Council. Contact Council for details of kerb profiles. TSD-R15: All kerb and channel in new or existing pavement to be constructed on a sub-base with minimum depth of 150mm in accordance with note 1. 		
<u>SORELL COUNCIL</u> <ul style="list-style-type: none"> TSD-R17: Concrete Kerbs And Channels Grated Wedge Crossings TSD-R19: Bluestone Kerbs And Channels Construction Details TSD-SW13: Side Entry Pits Table Drain Pit Construction TSD-SW22: Inlet Headwalls (Square) Raised Grated Inlet TSD-SW23: Inlet Headwalls (Domed) Raised Grated Inlet 		
<u>SOUTHERN MIDLANDS COUNCIL</u> <ul style="list-style-type: none"> No departures or exclusions 		

TASMANIAN STANDARD DRAWING AMENDMENT DATA SHEET

TASMANIAN STANDARD DRAWING AMENDMENT DATA SHEET

PROJECT TEAM AUTHORISATIONS

PROJECT TEAM AUTHORISATIONS

ACTIVITY	NAME	DATE	SIGNATURE
Northern Representative	_____	_____	_____
North-Western Representative	_____	_____	_____
Southern Representative	_____	_____	_____
L.G.A.T Representative	_____	_____	_____
Engineering Officer Technical Drafter	_____	_____	_____
Document Controller	_____	_____	_____

ACTIVITY	NAME	DATE	SIGNATURE
Northern Representative	_____	_____	_____
North-Western Representative	_____	_____	_____
Southern Representative	_____	_____	_____
L.G.A.T Representative	_____	_____	_____
Engineering Officer Technical Drafter	_____	_____	_____
Document Controller	_____	_____	_____

Amendment/Revision Number:

Amendment/Revision Number:

AMENDED DRAWINGS LIST:

AMENDED DRAWINGS LIST:

- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____

- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____
- _____

SCALES: AS SHOWN
(All scales are correct at A3)

REFERENCES

© 2012
This drawing and the information it contains is, and remains the property of the Local Government Association of Tasmania, and may only be used for the purpose of which it was intended. Reproduction of this drawing or its content in any format other than printed hard copies is strictly prohibited.
It is the users responsibility to ensure this drawing is the current version. The current version can be downloaded from: www.lgat.tas.gov.au



TAS Division
IPWEA
INSTITUTE OF PUBLIC WORKS
ENGINEERING AUSTRALIA



**STANDARD DRAWING
AMENDMENTS DATA SHEET**

GPO Box 1521, Hobart Tasmania 7001 | 326 Macquarie Street, Hobart Tasmania 7000
T: 03 6233 5966 F: 03 6233 5986 Email: admin@lgat.tas.gov.au

ISSUE DATE: 30-11-2013

DWG No. TSD-A01-v1

XRef File: TSD-A01-v1.dwg